

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०
BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.
(A Govt. of Bihar Undertaking)

ISO 9001: 14001; OHSAS 18001

Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna-800004

Tel. No.: 0612-2660850 • Fax No.: 0612-2660256

E-mail: bseidc@gmail.com • website: <http://www.bseidc.in> • CIN U80301BR2010SGC015859

दर आमंत्रण हेतु अल्पकालीन कोटेशन आमंत्रण सूचना संख्या-25 वर्ष-2020-21

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि० पटना के निबंधित संवेदकों/ख्याति प्राप्त फर्मों/कंपनियों से दिनांक:- 17.02.2021 के अपराहन 03:00 बजे तक राज्य के विभिन्न जिलान्तर्गत विभिन्न निर्माण कार्यो में प्रयोग हेतु Sports Infrastructure Items से संबंधित कार्यो हेतु गैर अनुसूचित मदों की आपूर्ति एवं अधिष्ठापन के लिए निम्नांकित मदों हेतु मुहरबंद कोटेशन अधीक्षण अभियंता, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०, पटना के कार्यालय में प्राप्त किया जाएगा एवं उसी दिन अपराहन 03:30 बजे कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष खोला जाएगा।

Sl. No.	Description of items	Qty	Unit	Rate In Digits	Rate In Words
1	Construction of Long Jump & Triple jump pits incl. sand filling as per IAAF drawing including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	Job		
2	Construction of Steeplecase pit inside North D portion as per IAAF drawing including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	Job		
3	Providing and laying Synthetic Athletic Track of Full PUR System having a minimum thickness of 15mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. Normal Stress Areas. The thickness of finished track surface should not be less than 15mm	1.00	Sqm		
4	Providing and laying Synthetic Athletic Track of Full PUR System having a minimum thickness of 20 mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. High Stress Areas with a minimum thickness of 20mm of finished track surface.	1.00	Sqm		

5	Providing and laying Synthetic Athletic Track of Full PUR System having a minimum thickness of 25 mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. High Stress Areas with a minimum thickness of 25mm of finished Track Surface	1.00	Sqm		
6	Providing and laying Synthetic Athletic Track of Sandwich type System having a minimum thickness of 15mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. Normal Stress Areas. The thickness of finished track surface should not be less than 15mm	1.00	Sqm		
7	Providing and laying Synthetic Athletic Track of Sandwich type System having a minimum thickness of 20 mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. High Stress Areas with a minimum thickness of 20mm of finished track surface.	1.00	Sqm		
8	Providing and laying Synthetic Athletic Track of Sandwich type System having a minimum thickness of 25 mm with valid product approval certificate and laboratory test certificates from World Athletics (IAAF) including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) and Class-II certification including all taxes and carriage etc. all complete job as per direction of E/I. High Stress Areas with a minimum thickness of 25mm of finished Track Surface	1.00	Sqm		
9	Providing and laying 400mtr length alluminium curbing as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Aluminium curbing	1.00	Each		
10	Providing & fixing Discuss Cum Hammer Cage 7 m to 10 m high manufactured from stable alluminium profile and fitted with a high quality safety net. The uprights for large safety cage are made from high quality oval alluminium profile 120 x 100 mm wall thickness 4 to 6 mm as an additional reinforcement the 10 m uprights are strengthened with internal special alluminium profiles cage should comprises of 6 uprights of 7 m, 4 uprights of 10m , 2 gates, 10 handles, 6 hinges, 10 spacer, 2 trolleys for adjustable gates, 11 safety net include 12 fastening ropes, stainless steel wire for start and end to fix the net correctly to the gate as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Discuss-cum-Hammer Throwing Cage	1.00	Each		

11	Supplying and installation of competition equipment as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Discuss Throwing Ring	1.00	Each		
12	Supplying and installation of competition equipment as per requirements / specifications laid down by IAAF including all taxes and carriage etc. all complete job as per direction of E/I. Discuss Throwing Cage	1.00	Each		
13	Providing & fixing Discuss cum Hammer Ring with concentric circle is rolled precisely with diameter of 2.50 m include centre point and marking for leveling of the concrete surface side as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Hammer Throwing Ring	1.00	Each		
14	Providing & Fixing Shot Put Ring is Rolled precisely with a diameter of 2.135 m include centre point of marking for leveling of the concrete surface insid as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Shot Put Ring	1.00	Each		
15	Providing & fixing Pole Vault Boxes made by stainless steel 3mm thick front section 5 mm thick rounded including ground anchors of drainage pipe per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Pole Vault Box	1.00	Each		
16	Supplying and installation of competition equipment as per requirements / specifications laid down by IAAF including all taxes and carriage etc. all complete job as per direction of E/I. Cover for Pole Vault Box	1.00	Each		
17	Providing & fixing Take of Board with solid wood 122 x 34 x 10 cm for Long & High Jump in two sections including in lay board 122 x 100 x 15 mm as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Take off Board for Long Jump	1.00	Each		
18	Supplying and installation of competition equipment as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Take off Board for Triple Jump	1.00	Each		
19	Supplying and installation of competition equipment as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Stop Board for Shotput	1.00	Each		
20	Providing & Fixing Steeple Chase Water Barrier with water jump steeple chase hurdles with height adjustable aluminium bases. Aluminium inner vertical profile 80 x 80 mm and outer vertical profile 86 x 86 mm the top quality upper cross bar as per requirements / specifications laid down by World Athletics (IAAF) including all taxes and carriage etc. all complete job as per direction of E/I. Steeple Chase with Hurdle	1.00	Each		

21	Providing and fixing informative sign boards in rectangular shape of size 1.20m x 0.90m made out of 16 gauge Aluminum panel bonded with IRC Specified colour of retro reflective sheeting of Type IV High Intensity Micro- Prismatic Grade Sheeting (HIP) having pressure sensitive / heat activated adhesive, IRC Specified colour retro reflective cutout border & messages having pressure sensitive adhesive having border & messages in IRC Specified colour backlogramround including M.S. angle iron frame of size 35 mm X 35 mm X 3 mm & two M.S. angle iron post of size 65 mm X 65 mm X 6 mm, 3.65 m long, duly painted with flat oil paint having alternate black and white bands of 25 cm width including G.I. fixtures etc; fixing the boards in M-20 concrete block of size 60cm X 60cm X 75cm including transportation etc; complete. Aluminum Panel Type IV High Intensity including all taxes and carriage etc. all complete job as per direction of E/I.				
22	Providing and laying polypropylene fibers Geotextile separation barrier 140/150 GSM, as per the standard procedure as per the enclosed specifications complete as required.	1.00	Sqm		
23	Providing and laying perforated ISI mark PVC pipe including end cap & jointing, as per direction of Engineer-in-charge: 150mmID (@10kg/sq. cm pressure)	1.00	Mtr.		
24	Supply and Installation of synthetic artificial turf for a football field of 105 x 68mts from a FIFA preferred producer having permeable backing, pile height 50mm, polyethylene monofilament, including customs clearance, insurance. Including rubber & silica sand as per manufacturer's recommended quantities, unloading and staging of rolls, sewing of seams, infilling with appropriate dispensing, spreading and levelling equipment, brushing of fibres with all poly-hydraulic controlled equipment, with pre tufted lines for centre and perimeter, FIFA Quality certification including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	Sqm		
25	Supply and installation of FIFA approved goalposts including net including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	Pair		
26	Supplying and installation of Synthetic Hockey Turf with Polyethylene texturized monofilament of 18mm pile height, sand dressed & polypropylene woven backing complete with 15mm cast in-situ shockpad and FIH certification including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	sqm		
27	Supplying and fixing of aluminum goal post for Hockey as per drawing, design and specifications approved by FIH including all fittings and net etc. including all taxes and carriage etc. all complete job as per direction of E/I.	1.00	pair		
28	Providing, Supplying & Fixing of Pumps- 10 H.P. Single stage centrifugal pump with pre All pump parts manufactured of engineering plastics to prevent problems with corrosion. Diffuser body made of Luranyl and impeller made of Noriy with fiberglass, for superb resistance and finish. Mechanical seal in AISI-316 stainless steel and silicon carbide. 3 working and 1 standby Make :Aquanomics/Emaux/Aqua all complete work of approved make as per direction of E/I.	1.00	No		

29	Providing, Supplying & Fixing of Filter With Top mounted MPV filter anufactured in FRP Sand filters, laminated with polyester/fibreglass resin. Comes in ivory. Equipped with collectors of 1" diameter and diffuser of highly resistant PVC and PP plastic. Fitted with pressure gauge, manual air and water purge valves. Screw less cover for quick opening and closing. Filter Dia 2300 MM Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
30	Providing, Supplying & Fixing of 110 mm dia Pool Inlet Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
31	Main Inlet Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
32	Providing, Supplying & Fixing of 110 mm dia Pool Drain Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
33	Providing, Supplying & Fixing of 63 mm dia Pool Vacuum Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
34	Providing, Supplying & Fixing of 16 mm dia Pool Overflow Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
35	Providing, Supplying & Fixing of 160 mm dia Suction Pipe all complete work of approved make as per direction of E/I.	1.00	Mtr		
36	Providing, Supplying & Fixing of ABS Grating with Frame (Drain Cover) (300x300mm) Make-Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
37	Providing, Supplying & Fixing of ABS Grating with Frame (Drain Cover) (600x600mm) Make-Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
38	Providing, Supplying & Fixing of Pool Inlets in ABS Make- Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
39	Providing, Supplying & Fixing of Suction floor Type (in ABS) inlet Make-Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
40	Providing, Supplying & Fixing of Overflow channel cover Make-Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	mtr		
41	Providing, Supplying & Fixing of Control Panel for Recirculating Pump all complete work of approved make as per direction of E/I.	1.00	No		
42	Providing, Supplying & Fixing of Junction Box Make-Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
43	Providing, Supplying & Fixing of Main power MCB Bush Bar all complete work of approved make as per direction of E/I.	1.00	No		
44	Providing, Supplying & Fixing of Pipes and Fittings for Pump Room, in UPVC Make Supreme/Finolex all complete work of approved make as per direction of E/I.	1.00	LS		
45	Providing, Supplying & Fixing of Glass mosaic tiles all complete work of approved make as per direction of E/I.	1.00	sqm		

46	Providing, Supplying & Fixing of Ladders - SS 316, 42mm dia non slippery three step Make - Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
47	Providing, Supplying & Fixing of Ladders - SS 316, 42mm dia non slippery Four step Make- Aquanomics/Emaux/Aqva all complete work of approved make as per direction of E/I.	1.00	No		
48	Providing, Supplying & Fixing of Vacuum points in the Pool all complete work of approved make as per direction of E/I.	1.00	No		
49	Providing, Supplying & Fixing of Telescopic handle all complete work of approved make as per direction of E/I.	1.00	No		
50	Providing, Supplying & Fixing of Hose Cuff all complete work of approved make as per direction of E/I.	1.00	No		
51	Providing, Supplying & Fixing of Brush all complete work of approved make as per direction of E/I.	1.00	No		
52	Providing, Supplying & Fixing of Suction Head all complete work of approved make as per direction of E/I.	1.00	No		
53	Providing, Supplying & Fixing of Hose Pipe all complete work of approved make as per direction of E/I.	1.00	No		
54	Providing, Supplying & Fixing of Flatnet all complete work of approved make as per direction of E/I.	1.00	No		
55	Providing, Supplying & Fixing of Deepnet all complete work of approved make as per direction of E/I.	1.00	No		
56	Providing, Supplying & Fixing of 38 mm diameter SS-316 tube with flange both side with SS nut both to fix . The steps are made of Fiberglass with anti skid design and fixed with SS made nut bolts. (MAKE:Arrdevpools/ASTRALpools/Aqva/equivalent) all complete work of approved make as per direction of E/I.	1.00	No		
57	Providing, Supplying & Fixing of UltraViolet 135 V make Aqva all complete work of approved make as per direction of E/I.	1.00	No		
58	Providing, Supplying & Fixing of Automatic Dosing system all complete work of approved make as per direction of E/I.	1.00	No		
59	Providing, Supplying & Fixing of Dosing Tank all complete work of approved make as per direction of E/I.	1.00	No		
60	Providing, Supplying & Fixing of Under Water LED light made of ABS plastic and LED light bulbs inside of 14.4 watt with step down transformer. Surface mounted brackets and fixtures including individual wiring and circuit wiring. (MAKE:DAZZLE/Aquanomics/Emaux) all complete work of approved make as per direction of E/I.	1.00	No		
61	Providing, Supplying & Fixing of Submersible Pump 2 H.P. No. 1 For Plant Room Make : AMAPORTER all complete work of approved make as per direction of E/I.	1.00	No		

62	Providing, Supplying & Fixing of Recyclable floor cleaner with CF-75 cartridge filter and Kirloskar 1 hp SPOM pump single phase 2990 RMP selfpriming pump mounted on trolley with wheels etc. with all accessories. Hose pipe 40 mm dia and 15-meter length. Floor cleaner made of SS-316 / aluminum with size of 400 mm wide with bushes inside. all complete work of approved make as per direction of E/I.	1.00	No		
63	Providing & Supplying Chemicals , TCCA-90 all complete work of approved make as per direction of E/I.	1.00	kg		
64	Providing & Supplying Chemicals, HCL all complete work of approved make as per direction of E/I.	1.00	Ltr		
65	Providing & Supplying Chemicals, Copper Sulphate all complete work of approved make as per direction of E/I.	1.00	kg		
66	Providing & Supplying Chemicals , Fitkari all complete work of approved make as per direction of E/I.	1.00	No		
67	Providing & Supplying Chemicals ,Test Kit all complete work of approved make as per direction of E/I.	1.00	No		
68	Providing, Supplying & Fixing of Over flow lane binder stand made of mild Steel with wheels inside with height of 5feet and width of 9 feet. (make :arrdevpools/astralpool/equivalent all complete work of approved make as per direction of E/I.	1.00	No		
69	Providing, Supplying & Fixing of Back stroke indicator with two no's of Pole of 1.8 meter high made of ss 316 with Flange nut and bolts.on both side of Pool width 25 meter long. Make : arrdevpools/astralpools/aqva/equivalent all complete work of approved make as per direction of E/I.	1.00	set		
70	Providing, Supplying & Fixing of Back stroke indicator with rolling Balls with quick release mechanism on The 1.2 meter'ss 316 made poles on both Side of pool all complete work of approved make as per direction of E/I.	1.00	No		
71	Providing, Supplying & Fixing of Starting Block on both side of pool with height of 300- 600 mm from water. The size of podium is 500mm wide as per fina standard/ Marking of no's on all 4 side with SS340 made bottom framing. Make :Arrdevpools/astralpool) all complete work of approved make as per direction of E/I.	1.00	No		
72	Providing, Supplying & Fixing of Floating racing lane made of HD plastic with flaps to roll on water and lane remain at constant place. The floats are bind together with color scheme of FINA regulation. The inside is GI rope with nylon coating of 5 mm thick and both side the nut bolts quick release and tensioner made in SS316. Hook binder on both side of walls. Float diameter : 100mm Length of lane : 50 meter. (make :Arrdevpools/astralpool/Aqva) all complete work of approved make as per direction of E/I.	1.00	No		
73	Providing, Supplying & Fixing of Competition Lane Divider all complete work of approved make as per direction of E/I.	1.00	No		

74	Providing, Supplying & Fixing of Table Tennis TABLE - thick-25MM table is 2.74 m (9.0 ft) long, 1.525 m (5.0 ft) wide, and 76 cm (2.5 ft) high all complete work of approved make as per direction of E/I.	1.00	Table		
75	Providing, Supplying & Fixing of JUDO MAT - 2 M X 1 M X 50MM REGULAR (EP+JSR)all complete work of approved make as per direction of E/I.	1.00	Each		
76	Providing, Supplying & Fixing of TAIKWANDO MAT REGULAR - 1 M X 1 M X 30 MMall complete work of approved make as per direction of E/I.	1.00	Each		
77	Providing, Supplying & Fixing of BOXING RING - NATIONALall complete work of approved make as per direction of E/I.	1.00	Each		
78	Providing, Supplying & Fixing of WRESTLING MAT 2 M X 1 M X 60MM (JSR MAT)all complete work of approved make as per direction of E/I.	1.00	Each		
79	Providing, Supplying & Fixing of Basket ball pole movable and height adjustable international standard board size: 180cm x 105cm, 25mm transparent acrylic board standard pole extension 3.20 mtr, made of 6 inch square, base made of 4 x 2 inch pipe, heavy dunking ring & nylon net, pole padding onfrontandsides, wheelsize6x2 inch pvc, 6 portable battery boxes each side, these boxes would contain 600kg rubble (concrete) weight each side, best quality pu spray paint.all complete work of approved make as per direction of E/I.	1.00	Each		
80	Providing, Supplying & Fixing of Movable badminton pole, made of 40x40mm square pipe, 70 kg weight each side, adjustable rachid with net, fine quality spray pu paint. Make: apex sportsall complete work of approved make as per direction of E/I.	1.00	Each		
81	Providing, Supplying & Fixing of Movable volley ball pole, made of 3"/3.5" round pipe, 50 kg weight each side, height adjustable, rachid with net, fine quality spray pu paintall complete work of approved make as per direction of E/I.	1.00	Each		
82	Providing, Supplying & Fixing of Hand ball goal post international standard size 3mtr x 2 mtr x 1 mtr, made of 80 x 80 mm square pipe, back support pipe 33 mm round, wheel size: 6 inch x 2 inch made of pvc, best quality spray paint with nylon net.all complete work of approved make as per direction of E/I.	1.00	Each		
83	Providing, Supplying & Fixing of Net ball post - portable & movableall complete work of approved make as per direction of E/I.	1.00	Each		
84	Providing, Supplying & Fixing of CONVERGING CHEST PRESS (GL-7011) Weight Stack : 90 Kg Gross Weight : 190 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly.all complete work of approved make as per direction of E/I.	1.00	No		

85	Providing, Supplying & Fixing of CONVERGING SHOULDER PRESS (GL-7012) Weight Stack : 90 Kg Gross Weight : 245 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly all complete work of approved make as per direction of E/I.	1.00	No		
86	Providing, Supplying & Fixing of LATPULL DOWN & MID ROW (GL-7013) Weight Stack : 100 Kg Gross Weight : 220 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly all complete work of approved make as per direction of E/I.	1.00	No		
87	Providing, Supplying & Fixing of PEC FLY / REAR DELT (GL-7014) Weight Stack : 100 Kg Gross Weight : 200 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly all complete work of approved make as per direction of E/I.	1.00	No		
88	Providing, Supplying & Fixing of LEG EXTENSION & LEG CURL (GL-7015) Weight Stack : 90 Kg Gross Weight : 233 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly all complete work of approved make as per direction of E/I.	1.00	No		
89	Providing, Supplying & Fixing of ASSISTED CHIN DIP (GL-7016) Weight Stack : 90 Kg Gross Weight : 206 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly all complete work of approved make as per direction of E/I.	1.00	No		

90	Providing, Supplying & Fixing of BICEP & TRICEP (GL-7017) Weight Stack : 90 Kg Gross Weight : 220 Kg Frame : 11 Gauge Seat Back Pad : Apply the principal of ergonomics, The use of Honeycomb Technology a molding design, Fit the human body curve, make the load of movement evenly distributed for users to bring a higher degree of comfort. Handle : The use of soft TPV (Thermoplastic Vulcanized rubber) extrusion molding. The use of anti-sliding increase comfort, The ergonomic design will disperse the load of movement of pull and push evenly.all complete work of approved make as per direction of E/I.	1.00	No		
91	Providing, Supplying & Fixing of FUNCTIONAL TRAINER (GL-1110) Weight Stack : 100 Kg Each Side Gross Weight : 450 Kgall complete work of approved make as per direction of E/I.	1.00	No		
92	Providing, Supplying & Fixing of COUNTER BALANCE SMITH MACHINE (GL-1113) Counter Balanced Gross Weight : 308 Kg Size : 1450 X 2230 X 2180 mmall complete work of approved make as per direction of E/I.	1.00	No		
93	Providing, Supplying & Fixing of 45 DEGREE LEG PRESS (GL-1114) Gross Weight : 275 Kg Size : 2150 X 1610 X 1520 MM)all complete work of approved make as per direction of E/I.	1.00	No		
94	Providing, Supplying & Fixing of OLYMPIC FLAT BENCH (GL-451) Gross Weight : 105 Kg Size : 2150 X 1610 X 1520 MM Inbuilt Plate Storageall complete work of approved make as per direction of E/I.	1.00	No		
95	Providing, Supplying & Fixing of OLYMPIC INCLINE BENCH (GL-452) Gross Weight : 135 Kg Size : 2150 X 1610 X 1520 MM Inbuilt Plate Storageall complete work of approved make as per direction of E/I.	1.00	No		
96	Providing, Supplying & Fixing of OLYMPIC DECLINE BENCH (GL-453) Gross Weight : 120 Kg Size : 2150 X 1610 X 1520 MM Inbuilt Plate Storageall complete work of approved make as per direction of E/I.	1.00	No		
97	Providing, Supplying & Fixing of ADJUSTABLE BENCH (GL-454) Gross Weight : 56 Kg Positions : Flat / Incline / Decline Leg Lock Availableall complete work of approved make as per direction of E/I.	1.00	No		
98	Providing, Supplying & Fixing of PREACHER BENCH (GL-457) Gross Weight : 86 Kgall complete work of approved make as per direction of E/I.	1.00	No		
99	Providing, Supplying & Fixing of HYPEREXTENSION (GL-459) Gross Weight : 80 Kgall complete work of approved make as per direction of E/I.	1.00	No		
100	Providing, Supplying & Fixing of ADJUSTABLE AB BENCH (GL-458) Gross Weight : 96 Kgall complete work of approved make as per direction of E/I.	1.00	No		
101	Providing, Supplying & Fixing of FLAT BENCH (GL-456) Gross Weight : 44 Kgall complete work of approved make as per direction of E/I.	1.00	No		
102	Providing, Supplying & Fixing of ROUND DUMBBELLsall complete work of approved make as per direction of E/I.	1.00	No		
103	Providing, Supplying & Fixing of Changing room Lockers in MS, Locker with 12 Sections Total Size : Height - 78 inch, Width - 36 inch, Depth - 19 inch Each Locker Size - 17 inch x 11 inch all complete work of approved make as per direction of E/I.	1.00	Unit		

104	Providing, Supplying & Fixing of Canadian Maple Hardwood Sports Flooring "Certified by the BWF according to BWF standards - Grade 1" LABO SPORTS TEST CERTIFY finished with 21mm thick, 57 to 83mm wide and in random length in tongue and groove shape. The edges of the boards will have a finger lock groove and the bottom side with air pass groove and treated with special anti-termite and water-resistant lacquer.(Large Multipurpose Hall)all complete work of approved make as per direction of E/l.	1.00	Sqm	
105	Providing, Supplying & Fixing of seamless synthetic Polyurethane flooring over shock absorbing layer as approved by FIVB / FIBA / BWF (Small Multipurpose Hall) all complete work of approved make as per direction of E/l.	1.00	Sqm	

विशेष शर्तें -

- यह कोटेशन सिर्फ दर निर्धारण हेतु आमंत्रित किया गया है।
- कोटेशनदाताओं को अपना दर (सभी करों, GST एवं ढुलाई व्यय के साथ) अंक एवं अक्षरों में उद्धृत करना होगा।
- विशेष सूचना के लिए सूचनापट्ट या वेबसाइट www.prdbihar.gov.in एवं www.bseidc.in देखें अथवा अधोहस्ताक्षरी के कार्यालय में कार्यावधि में संपर्क किया जा सकता है।


 अधीक्षण अभियंता
 BSEIDC, पटना।