

Report on Sub Soil Investigation for the proposed  
**High School at Sonawaan, Block - Ghoshi, District Jehanabad**

**1. INTRODUCTION**

The subsoil investigations reported herein were taken up to find out the nature of subsoil at the site of the proposed construction and to recommend the capacity and type of its foundation. After certain tests on the soil, as detailed below, the desired recommendations have been made on **page 3** of this Report.

**2. FIELD WORK**

The fieldwork consisted of sinking a bore hole, conducting the necessary field tests in it and collecting soil samples from it for conducting laboratory tests on them.

**2.1. Boring**

Taking guidance from IS: 1892, one bore hole of 150 mm diameter was sunk at the location shown in the bore hole location map.

**2.2 Sampling**

**2.2.1 Undisturbed Soil Samples**

Open drive samplers of 100-mm diameter and about 450-mm length were used for obtaining undisturbed samples of cohesive soils. The collection, sealing, labeling and transportation of the samples to the laboratory were done as per the IS guide-lines.

**2.2.2 Disturbed Soil Samples**

Disturbed soil samples were collected from the bore hole at suitable intervals of depth (not more than 2.5 m) and at all depths of change in the nature of the subsoil. These samples were sealed in polythene bags with proper identification labels.

**2.3 Field Tests**

**2.3.1 Standard Penetration Tests (SPT)**

These tests were conducted as per IS: 2131 – 1963. The depth interval between two consecutive tests was 1 to 1.5 m. The tests were located in between the levels at which undisturbed soil samples were collected.

Report on Sub Soil Investigation for the proposed  
**High School at Sonawaan, Block - Ghoshi, District Jehanabad**

**3. LABORATORY TESTS**

Some or all of the following laboratory tests, as necessary, were done on the collected soil samples. Representative soil samples were selected for this from the different soil strata encountered during boring. The tests were performed as per the relevant Indian Standard Codes of Practice.

- (a) Natural moisture content
- (b) Bulk density
- (c) Grain size analysis (using sieves and / or hydrometer)
- (d) Specific gravity of soil solids
- (e) Atterberg's limit tests (liquid, plastic and shrinkage limits)
- (f) Shear Tests :
  - [I] Triaxial compression test (unconsolidated – undrained), generally for fine- grained soils
  - [II] Unconfined compression tests, only on cohesive soils
  - [III] Direct shear tests, generally for coarse-grained soils
- (g) Chemical tests on soil/ground water
- (h) Other tests as and when required.

**4. PRESENTATION OF TEST RESULTS**

The field and laboratory test results are given in the **Appendix - B**.

**5. SOIL STRATIFICATION**

The results of field tests in three bore holes sunk at the site [vide Location Sketch in App. A] and the results of laboratory tests conducted on the collected soil samples indicate that the soil stratification at the site is as describe below.

The subsoil in all BH's is sandy silty clay [type CL / CI] up to the depth of about 3.0 m followed by silty sand / sand [type SM-SP / SP] in variable thicknesses and variable sequences up to the investigated depth of 10.5 m bgl.

*Ground water table was struck at about 1.00 m to 1.10 m depth below GL in November, 2019. It is subject to seasonal variations.*

**6. FOUNDATION ANALYSIS**

The safe capacity of foundation of any type and size may be determined on the basis of the soil data given in this Report by using the standard methods of foundation design and following the relevant Indian Standard Codes.

Report on Sub Soil Investigation for the proposed  
High School at Sonawaan, Block - Ghoshi, District Jehanabad

## 7. RECOMMENDATIONS

The design of the foundation for the proposed structure depends on the nature of both [a] the subsoil and [b] the structure.

The subsoil in all BH's is sandy silty clay [type CL / CI] up to the depth of about 3.0 m followed by silty sand / sand [type SM-SP / SP] in variable thicknesses and variable sequences up to the investigated depth of 10.5 m bgl.

*Ground water table was struck at about 1.00 m to 1.10 m depth below GL in November, 2019. It is subject to seasonal variations.*

1. The proposed structure may be provided with shallow foundation at a depth of 2.0 m or more. As the formation up to over 2 m is very soft.
2. As the formation below 3 m depth is silt to silty sand. Hence placement of bored cast in situ pile or u/r pile may not be desirable as this formation may collapse during such pile placement. Driven piles may be uneconomical.

The values of net allowable bearing pressures of foundations of certain sizes have been calculated [vide sample of Calculation in Appendix - F] and are tabulated below.

**Table 1: Allowable Net Bearing Pressures [  $q_{na}$  ] and Settlements Expected [s]**

Depth (m) below GL	Width (m)	Net allowable bearing pressure (t/m <sup>2</sup> )			Maximum expected settlement (mm)
		Strip footing	Square footing	Raft foundation	
2.0	2.0	6.3	7.5	....	75
	3.0	5.5	7.1	....	75
	10.0	...	...	6.7	100
2.5	2.0	7.8	9.3	....	75
	3.0	6.1	8.8	....	75
	10.0	...	...	7.5	100
3.0	2.0	9.1	10.9	....	75
	3.0	6.9	10.1	....	75
	10.0	...	...	8.0	100
3.5	2.0	11.1	13.4	....	75
	3.0	7.2	12.6	....	75
	10.0	...	...	8.1	100

**Note:**

If a soil condition much different from those reported herein is met with during foundation trenching, suitable steps should be taken.

For Bihar Foundation Consultants,

(Dr. K.S.P. Singh, FIE, MIGS)  
Senior Consultant.