Schedule XLV - Form No. 61

Name of Work - Construction of Additional Class Rooms (2 Unit) at Uchchtar Madhyamik School, Barganiya, Block-Sikta, West Champan (ACR-240)

BIHAR PUBLIC WORKS DEPARTMENT

Agency - [Form No. F-2] Lakshmi Devi

ITEM RATE TENDER AND CONTRACT FOR WORKS

Agreement No. ———— 35 F_2 of 2019-20.

General Rule and Direction for the guidance of Contractors.

Date of Commencement - 08-03-2019.

1. All works proposed for execution by contract will be notified in a form of invitation to tender passed on a board hung up in the office of and signed by the Sub-divisional Officer/Executive Engineer.

This notice will state the work to be carried out the items and approximate quantities thereof as well as the date for submitting and opening tenders also, amount of earnest money to be deposited and the amount of the security deposit to be deposited by the successful tenderex and the percentage if any to be deducted from bills, copies of the specifications, designs and any other documents required in connection with this submission of tender signed for the purpose of identification by the Sub-divisional Officer/Executive Engineer shall also be open for inspection by the contractor at the office of the Sub-divisional Officer/Executive Engineer during office hours.

2. In the event of the tender being submitted by a firm, it must be signed separately by each member there of or in the event of the absence of any partner, it must be signed on his behalf by a person holding a power-authorising him to do so.

3. Receipt for payments made on account of work when executed by a firm must also be signed by the several partners, except where the contractors are described in their tender as a firm in which case the receipt must be signed in the name of the firm by one of the partners, or by some other person having authority to give effectual receipt for the firm.

4. The memorandum of work tendered or and the memorandum of materials to be supplied by the Public Works Department and their issue rates shall be filled in and completed in the Office of the Sub-divisional Officer/Executive Engineer before the tender form is issued. If a form is issued to a intending tender without having been so filled in and completed, he shall request the office to have this done before he complete and delivers his tender.

5. The amount of earnest money to be deposited will be : -	Rs.
If the amount of the estimate does not exceed Rs. 2,000	50
If the amount of the estimate exceeds Rs. 2,000 but does not exceed Rs. 5,000	100
If the amount of the estimate exceeds Rs. 5,000 but does not exceed Rs. 10,000	200
For each additional Rs. 5,000 or portion of Rs. 5.000 additional earnest money	100

6. Any Person who submits a tender shall fill up the usual printed form stating there at what rate he is willing to undertake each item of the work incomplete tender and tenders which propose any alteration in the work specified in the said form of invitation tenders, or which contain any other conditions of any sort, or omit to note the time within which the work can be finished, or which are not accompanied by the treasury challan for the required earnest money will be liable to rejection. No single tender shall include more than one work, but contractors who will to tender for two or more works shall submit a separate tender for each Tender shall bear the name of the work to which they refer written outside the envelop. Cash deposits for earnests money here in before mentioned shall be made in Government Treasuries and the challan there of should be enclosed with the tender.

Chief Engineer
Bihar State Educational Infrastructure Development Corporation Ltd., Patna

7/8/19

7. The Engineer or his duly authorised assistant will open the tender in the presence of any intending contractors who may be present at the time and will enter the amounts of the several tenders a comparative statements in a suitable form. In the event of a tender being rejected the challan for the earnest money forwarded therewith shall there upon be returned to the tenderer with a pay order for the amount of the earnest money.

8. The Engineer shall have the right of rejecting all or any of the tenders.

9. In the event of a tender being selected for acceptance the Engineer who opened the tenders will, if he is competent to accept the tender, inform the tenderer or the selected tender who shall thereupon sign copies of the specification & other documents mentioned in rules 1 and 4 for the purpose of identification and for his acceptance with the tender. The tenderer of the selected tender shall also deposit the required amount of the security money within the prescribed time. If the tenderer fails to deposit the required amount of the security money within the prescribed time, the Engineer may reject the tender.

If the Engineer is not competent to accept the tender himself, he will inform the tenderer of the tender which he decides to recommend for acceptance. Such tenderer shall thereupon sign forth- with copies of the specification and other documents mentioned in rules 1 and 4 and shall deposit the required amount of the security money within the priscribed time. The tender with the specilication and other documents signed by the tenderer will then be forwarded for acceptance and the security money deposited shall be refunded to the tenderer.

10. When a tender is selected for acceptance the tender shall deposit the required amount of the security money in cash in the treasury and shall forward the challan to the Executive Engineer, Government securities may be endorsed to the Executive Engineer lieu of a cash deposit of the required amount of the security money. No tender shall be finally accepted until the required amount of the security money has been deposited.

11. The amount of security money to be deposited by the tenderer whose tender is selected for acceptance shall be 10% of the estimated value of the work & towards this amount the earnest money already deposited by him shall be credit. At least half of this security inclusive of the earnest money shall be deposited by the tenderer within such time as may be notified to him in writing by the officer opening tender, failing which the tender shall be liable to rejection.

Any balance of the security money outstanding after completion of the contract with the tenderer may be made up by deductions of 5% of the amount of each payment to be made to him under clause 7 of the conditions of contract for work done under the contract.

12. When a tender has been selected for acceptance & the required amount of the security money has been deposited the Engineer shall scrutinise all pages of the form of item, rate, tender & contract for works to see that the form has been properly filled up and signed by the contractor & the signature witnessed He shall then if he is competent, to accept the tender, sign the acceptance of the tender, or, if he is not so competent shall send the form for signature of the acceptance of the officer competent to accept it.

Chief Engineer
Irrigation Deptt. Patna

Schedule XLV - Form No. 61 (3)

TENDER FOR WORKS

I/We: hereby tender for the execution for the Governor of Bihar of the work specified in the under written memorandum at the rates specified therein within a period of years month from the date of written order to commence and in accordance in all respects with the specifications designs, drawing, and other documents referred to rule hereof and Subject to the annexed conditions of contract and with such materials as are provided for by and in other respects in accordance with, such conditions so far as applicable.

MEMORANDUM

(a) If several sub-work are included they should be detained in a separate list.

[a] Name of work .....

[b] Estimated cost .....

(b) This deposit will be 5% of the estimated cost of the Work.

[c] Earnest money .....

[d] Initial security deposits (including earnest money) to be deposited befor the commencement of the work .....

(c) This percentage deduction from bills will be credited to the contractors security deposit.

[e] Percentage to be deducted from bills Rs. 5% (Rupees five percent)

[f] Time required for the work from date of written order to commence .... monthly

[g] Date of written other to commence

[h] Total number of item of work tendered for

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	

Schedule XLV - Form No. 61

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	

Schedule XLV - Form No. 61

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	

should this tender be accepted I/we hereby agree to abide by and fulfill all th terms and provisions of the said conditions of contract annexed hereto so. for a applicable, or in ssors in office the sums of money mentioned in the said conditions

Dated the day of 20

*Signature, of contractor before comission of tender

witness

Address

Occupation

Signature of witness to contractor's signature

The above tender is hereby accepted by me on behalf of the Governor of Bihar

Dated the day of 20

signature of the office accepting the tender

Acceptances communicated on.....

लक्ष्मी देवी

signature of the party taking the tende

—●●—

CONDITIONS OF CONTRACT

Compensation

Clause 1:- All compensation or other sums of payable by the contractor to Government under the terms of his contract may be deducted from, paid by the sale of a sufficient part of his security deposit or from the Interest arising therefore or from any sums which may be due or may become due to the contractor by Government on any account whatsoever and in the event of his security deposit being reduced by reason of any such deduction or sale as aforesaid, the contractor shall within ten days there after make good in cash or Government securities endorsed as aforesaid any sum or sums which may have been deducted from, or arised by, sale of his security deposit of any part thereof.

The work should not be considered untill such date as the Executive Engineer shall certify as the date on which the work is finished after necessary rectification of defects as pointed by the Executive En- gineer or his authorised agents are fully contractor to the Engineer's satisfaction.

Clause 2 :- The time allowed for carrying out the work as entered in the tende shall be strictly observed by the contractor and shall be reckoned from the date on which the wirtten order to comence work is given to the contractor. The work shall throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the contract on the part of the contract or) and the contractor shall pay as compensation an amount equal to ½ percent on the amount of the estimated cost of the whole work as shown by the tender for every day that the work remains uncommenced or unfinished after the proper date. And further to ensure good progress during the execution of the work the contractor shall be bound in all cases in which the time allowed for any work exceeds one month to complete one fourth of the whole of the work before one - fourth of the whole time allowed under the contract has elapsed one-half of the work before one-half of such time elapsed and three-fourths of the work, before three fourths of such time has elapsed in the event of the contractor failing to employ with this condition, I shall be liable to pay as compensation an amount equal to ½ percent on the said estimated cost of the whole work for every day that the due quantity of work remains incomplete provided always that the entire amount of compensation to be paid under the provisions the clause shall not exceed 10 percent of the estimated cost of the work as shown in the tender.

Action when persnle security deposit foreited

Clause 3 :- In any case which under any clause or clauses of or this contract the contractor shall have rendered himself laible to pay compensation amounting to the whole of his security deposit in the hands of Government (where paid in one sum or deducted by instalments) the Executive Engineer on behalf on the Bihar Government shall have been powered to adopt any of the following courses, as he may deem best suited to the enterest of Government -

लक्ष्मी देवी

(a) To rescind the contract (of which rescind notice in writing to the contractor under the hand of the Executive Engineer shall be conclusive evidance) and in which case the sectitiry deposit of the contractor shall start forfeited, and be absolutely at the disposal of Government.

Chief Engineer BSEIDC Ltd Patna

7/8

(b) To employ labour paid by the Public Works Department and to supply materials to carry out the work, or any part of the work, debitting the construction with the cost of the labour and the price of the materials (of the amount of which cost and price certificate of the Engineer-in -charge shall be final and conclusive against the contractor), and crediting him with the value of the work done, in all respects in the same manner and at the same rates as if it had been carried out by the contractor under the terms of his contract, the certificate of the Executive Engineer as to the value of the work done shall be final and conclusive against the contractor.

(c) To measure up the work of the contractor and to take such part of the work of the contractor as shall be unexecuted out of his hands, and to give it to another contractor to complete in which case any expenses which may be incurred in excess of the sum which would have been paid to the original contractor if the whole work had been executed by him (of the amount of which excess the certificate in writing of the Executive Engineer shall be final and conclusive) shall be born and paid by the original contractor and made be deducted from any money due to him by Government under the contract or otherwise, or from his security deposit or the proceeds of sale thereof, or a sufficient part thereof.

In the event of any of the above courses being adopted by the Executive Engineer, the contractor shall have no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials or entered into any engagement, or made advances on account of or with a view to execution of the work or the performance of the contract. And in case the contract shall be rescinded under the provision aforesaid, contractor shall not be entitled to recover or be paid any sum for any work there-to-fore actually performed under this contract unless and until the Executive Engineer shall have certified in writing the performance of such work and the value payable in respect thereof and he shall only be entitled to be paid the values so certified.

contractor remains liable to pay compensation if action not take under cause 2.

Clause 4 :- In any case in which any of the powers, conferred upon the Executive Engineer by clause 3 thereof shall have become exercisable and the same shall not be exercised the non-exercise there of shall not contitury waiver of the conditions here and such power shall not with standing be exercisable in the event of any future case of default by the contractor for which by any clause or clauses hereof he is declared liable to pay compensation amounting to the whole of his security deposit and the liability of the contractor for past and future compensation shall remain unaffected in the event of the Executive Engineer putting in force the powers vested in him under the preceeding clause he may. if so desires, take possession of all or any tools, plants, materials and store, in or upon the works of the site thereof or belonging to the contractor or procured by him and intended to be for the execution of the work or any part there of paying or allowing for the same in the contract at the account rates, or in case of these not being applicable at current market rates to be certified by the Executive Engineer whose certificate thereof shall be final, otherwise the Executive Engineer may notice in writing to the contractor or his clerk of the work, foreman or other authorised agent require him to remove such tools, plants, materials or stores from the premises (within a time to be specified in such notice) and in the event to the contractor failing to comply with any such requisition the Executive Engineer may remove them at the contractor expense or sell them by auction or private sale on account of the contractor and at his risk in all respect, and the certificate of the Executive Engineer as to the expense of any such removal and the amount of the proceeds and expense of any such sale be final and conclusive against the contractor.

Power to take posession of or require removal of or sell contractor plant.

Clause 5 :- If the contractor shall desire any extension of the time for completion of the work on the ground of his having been unavoidably hindered in its execution or on any other ground other than those mentioned in clause 12 (a) he shall apply in writing to the Executive Engineer within 40 days from the date of starting of the hinderance on account of which be desires such extension as aforesaid and the Executive Engineer shall, if in his opinion (which shall be final) reasonable grounds be shown thereof authorised such extension of time if any, as may in his opinion be necessary or proper. The Executive Engineer shall at the same time inform the contractor whether he claims compensation for the delay.

Extension of time

27/08/11
Chief Executive Officer
B.S.E.I.D.C. Ltd, Patna

लक्ष्मी देवी

2
7/8

Final certificate

Clause 6:- On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (herein after called the Engineer-in-charge) of such completion, but no such certificate be given, nor shall the work be considered to be complete until the contractor no such certificate be given, nor shall the work be considered to be complete until the contractor shall have removed from the area of the premises (to be distinctly marked by the Executive Engineer in the site plan) on which the work shall be executed all scaffolding surplus materials, and rubbish, and cleaned of the dirt from all wood-work doors, windows, walls, floors or other parts of any building, in upon or about which the work is to be executed, or of which he may have had possession for the purpose of the execution thereof, not until the work shall have been measured by the officer of the Public Work Department in accordance with rules of Department whose measurements shall be binding and conclusive against the contractor. If the contractor shall fail to comply with the requirements of this clause as to removal of scaffolding, surplus materials and rubbish and cleaning off dirt on or before the date fixed for completion the work the Engineer-in-charge may at the expense of the contractor remove such scaffolding, surplus materials and rubbish and dispose of the same as the thinks fit and clean of such dirt as aforesaid, and the contractor shall forth with pay amount of all expense so incurred, and shall have no claim in respect of any such scaffolding or surplus materials as aforesaid, except for any sum actually realised by the sale thereof.

Payment of in terms date certificate to be regarded as advance and Bill to be submitted monthly.

Clause 7:- A bill shall be submitted by the contractor each month or before the date fixed by the Engineer-in-charge for all work executed in the previous months and the Engineer-in-charge or his subordinate shall take the requisite measurement for the purpose of having the same verified and the claim, as for as admissible, adjusted, if possible before the expiry of the days from the presentation of the bill. If the contractor does not submit the bill within the time fixed as aforesaid, the Engineer in-charge or his subordinate shall measure up the said work in the presence of the contractor whose counter whose counter signature on the measurement list will be sufficient warrant, and the Engineer-in-charge or his subordinate shall prepare at bill from such list which shall be binding to the contractor in all respects.

Provided that, if any balance of the 10% security is outstanding from each such payment shall be deducted so much not exceeding 5% may be necessary to make up the balance of the security. All such intermediate payment to the contractor shall be regarded as payments by way of advance against the final payments only and not as payments for work actually done and completed and shall not precinde the reputing of bad, unsound and imperfect or unskilful work to be removed and taken away and reconstructed or recreated be considered as an admission of due performance of the contractor, or any part thereof in any respect, or the actual of any claim nor shall conclude, determine or affect in any way the powers of the Engineer-in-charge under these conditions or any of them as so the final settlement or adjustment of the account or in any other way vary or affect the contract.

Clause 8:- The final bill shall be prepared by the officer of the Public Work Department in accordance with the rules of the department in the presence of the contractor within the month of the date fixed for completion of the work.

Stores supplied Government

Clause 9:- If the specification or estimate of the work provides for the use of any special description of material to be supplied from the Engineer in-charge's stores or if it is required that the contractor shall use certain stores to be provided be the Engineer-in-charge under the conditions of this contract or (such materials and stores, and the prices to be charged therefore as herein after mentioned being so far as practicable for the convenience of the contractor, but not so as in any way to control the meaning or effect of this contract are specified in schedule or memorandum here to annexed) the contractor shall be supplied with such materials and stores noted in the annexed such schedule required from time to time to be used by him for the purposes of the contract, only and the value of the full quantity of materials and stores so supplied at the rates specified in the said schedule may be set off or deducted from any sums then due or there after to become due to the contractor under the contract or otherwise, or against or form the security deposit, or the proceed of sale thereof, if the same is held in Government security the same or sufficient portion thereof in this case sold for the purpose. All materials supplied to the contractor shall remain the absolute property of Government and shall not on any accounts he removed from this site of the work and shall at all times be open to

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

inspections by the Engineer-in-charge. Any such materials unused and in correctly in good condition at the time of the completion or determination of the contract shall be returned to the Engineer-in-charge's store, at the prevailing market rate or at the issue rate whichever is less if by a notice in writing under his hand he shall so require, but the contractor shall not be entitled to return any such materials unless with such consent and shall have no claim for compensation on account of any such materials so supplied to him as aforesaid being unused by him, or for any wastage to or any such materials.

Work to be executed accordance with specification drawing other etc.

Clause 10 :- The contractor shall executive the whole and every part of the work in the most substantial and workman like manner, and both as regards materials and otherwise in every respect in strict accordance with the specifications. The contractor shall also confirm exactly, fully and faithfully to designs, drawings, and instructions in writing relating to the work singed by the Engineer-in-charge and lodged in his office and to which the contractor shall be entitle to access at such office, for the purpose of inspection during office hours, and the contractor shall, if he so require be entitled at his own expenses to make or cause to be made copies of the specification, and of all such designs, drawings and instructions as aforesaid.

Alteration in specifications and designation.

Clause 11 :- Engineer-in-charge shall have power to make any alteration in additions to the original specifications, drawings and instructions that may appear to him to be necessary or advisable during the progress of the work. The contractor shall be bound to carry out the work in accordance with any instructions which may be given to him in writing signed by the Engineer-in-charge, and such alteration shall not invalidate the contract and any additional work which the contractor may be directed to do in the manner above specified as part of the work shall be carried out by the contractor on the same conditions in all respects on which he agreed to do the main work, and at the same rates as are specified in the tender of the main work. The time for completion of the work shall be extended in the proportion that the additional work bears to the original contract work and the certificate of the Engineer-in-charge shall be conclusive as to such proportion and to the additional work includes any class of work, for which no rales is specified in this contractor then such class of work shall be carried out at the rates entered in the sanctioned schedule or rates of the locality during the period when the work is being carried on and if such last mentioned class of work is not entered in the schedule of rates of the district then the contractor shall within seven days of the date of his receipt of the order to carry out the work inform the Engineer-in-charge does the rate which in his intention to charge for such class of work and if the Engineer-in-charge does not agree to this rate he shall be noticed in writing be at liberty to cancel his order to carry out such class of work and arrange to carry it out in such manner as he may consider advisable provided always that if the contract shall commence work or in our any expenditure in regard thereof before the rate shall have been determine as lastly herein before mentioned then and in such case he shall only be entitled to be paid in respect of the work carried out or expenditure incurred by him prior to the date of the determination of the rates as aforesaid according to such rate or rates as shall be fixed by the Engineer-in-charge in the event of a disputes the decision of the superintending Engineer of the circle will be final.

Do not in validate contract

Time in consequence of alteration

Provided always that the contractor shall not be entitled to any payment for any additional work done unless he has received an order in writing from the Engineer-in-charge for the additional work the contractor shall be bound to submit his claim for any additional work done during any month on or before the 15th days other following month accompanied by a copy of the order in witting of the Engineer-in-charge for the additional work and that contractor or shall not be entitled to any payment in respect of such additional work if be other submit his claim within date afore said period.

Rate for work no in estimate or schedule of rates of the district.

Clause 12:- If at any time after the commencement of the wok the Government of Bihar shall for any reason whatsoever not require the whole thereof as specified in the tender to be carried out. the Engineer-in-charge shall give notice in writing of the fact to the contractor who shall have no claim to any payment of compensation whatsoever on account of any profit or advantage, which he might have derived from the execution of the work in full, but which he did not derive in consequence of the full amount of the work not having been carried out neither shall he have any claim for compensation by reason of any alternation having been made in the original specification, drawing, designs and instruction which shall involve any installment of the work as originally contemplated clause 12 (a) As contained in G O 1929 dated 11.9.56.

Compensation for alteration in or restriction of work to be carried out.

Chief Engineer
B.S.E.B.C. Bld, Patna

मनोहरी देवी

Clause 12 (a) The contractor shall not be entitled to claim any compensation for loss suffered by him on account of delay by or on behalf of Government in the supply of materials as stores which the Government may have undertaken to supply where such failure is due to :-

(i) natural calamities, (ii) act of enemies, (iii) transport and procurement difficulties or (iv) circumstances beyond the control of the state Government.

In case of such failure in delay in the supply of materials or stores on an application by the contractor within 30 days form the date of such failure or delay, such extension of time shall be granted to the contractor for completion of the work as shall appears to the Engineer to be reasonable in accordance with the circumstances of the case. The decision of the Executive Engineer as to the extension of time shall be accepted as finally by the contractor.

Action and compensation payable in case of work.

Clause 13 :- If it shall appear to the Engineer-in-charge or his subordinate in charge of the work that any work has been executed with unsound, imperfect or unskilful workmanship or with materials of any inferior description, or by any materials or articles provided by him for the execution of the work are unsound or of a quality inferior to that contracted for at otherwise not in accordance with the contract, the contractor shall on demand in writing form the Engineer-in-charge specifying the inadverentaly passed certified and paid for, forthwith rectify or remove and re-contract the work so specified in whole or in part as the case may remove the materials or articles so specified and provided other proper and suitable materials or articles at his own proper charge and cost, and in the event of failing to do so within period to be specified by the Engineer-in-charge in his demand aforesaid the contractor shall be laible to pay compensation at the rate of one percent, on the amount of the estimate for every day not exceeding ten days while his failure to do so shall continue and in the case of any such failure the Engineer-in-charge may certify or remove, and re-execute the work or remove and replace with others, the materials or articles complained of as the case may be.at the risk and expense in all respects of the contractcor.

Work to be taken to inspection

Clause 14 :- All work under in course of execution or executed in presence of the contractor shall at the times be open to the inspection and supervision of the Engineer in-charge and his subordinates and the contractor shall at all times during the usual working hours and at all other time at which reasonable notice of the intimation of the Engineer-in-charge or his subordinate to visit the works shall have been given to the contractor, either himself to be present to receive orders and instruction, or have a responsible agent duly credited in writing present for that purpose orders given to the contractor's agent all shall be considered to have the same force as if they had been given to the contractor himself.

Contractor or responsible Agents to be present.

Clause 15 :- The contractor shall give not less than five days notice in writing to the Engineer-in-charge or his subordinate-in-charge of the work before covering up or otherwise placing beyond the reach of measurement of any work in order that the same may be measured and correct dimensions there of be taken before the same is so covered up or placed beyond the reach of measurement and shall not cover up or place beyond the reach of measurement of any work without the consent in writing of the Engineer-in-charge or his subordinate in-charge of the work shall be covered up or placed beyond the reach of measurement without such notice having been given or consent obtained, the same shall be uncovered at the contractor's expenses or in default there on payment or allowance shall made for such work on materials with which the same was effected.

Notice to be taken before work covered up

Clause 16:- If the contractor or his work-people, or servants shall break, deface injure or destroy any part of a building in which they may be working or any building, road, road curves, fence enclosure water pipes, cables, drains, electric or telephone posts or wires, trees, grass or grassland or cultivated ground contiguous on which the work or any part of it is being executed or if any damage shall happen to the work, while in progress from any cause whatsoever or any imperfection become apparent in if within three months (six months in the case of a road-work) after a certificate final or other of its completion shall have been given by the Engineer-in-charge

Chief Engineer
B.S.E.I.D.C. Ltd. Patna

Schedule XLV - Form No. 61

as a fore seal, the contractor shall make the same good at his own expense, or in default, the Engineer-in-charge may cause the same to be made be good by other workmen and deduct the expense of which time thereafter may become due to the contractor, or from his security deposit, or the proceed of sale there of, or of a sufficient portion there of the security deposit at the contractor shall not be refunded before the expiry of three months (six months in the case of a road-work) after the issue of the certificate final or otherwise of completion of work provided that in the case of a road work if in the opinion of the Engineer-in-charge behalf of the security deposit will be refundable after three months of the issue of the said certificate of completion

Contractor liable for damage done and for imperfection a months and after certificate

Clause 17:- The contractor shall supply at his own cost all materials (except such special materials) if any as may in accordance with the contract be supplied from the Engineer-in-charges stores). Plants, tools, application, implements, ladders, cordage, tackle scaffolding and temporary works requisits or proper for the proper execution of the work whether original, altered or substituted and whether include in the specification or other documents forming part of the contract or referred to in these conditions or not or which may be necessary for purpose of satisfying or complying with the requirement of the Engineer-in-charge as to any matter as to which under these conditions he is entitled to be satisfied which he is entitled to require together with carriage therefore to and form the work. The contractor shall also supply without charge the requisite number of persons with the means and materials necessary for the purpose of setting out works, and counting, weighing and assisting in the measurement or examination at any time and form time to time of the work or materials failing his so doing the same may be Provided by the Engineer-in-charge at the expense of the contractor and the expenses may be deducted from any money due to the contractor under the contract from his security deposit or the proceeds of sale thereof or of a sufficient portion thereof. The contractor shall also provide all necessary fencing and lights required to protect the public from accident, and shall be bound to bear to expenses of defence of every suit action or other proceeding at law that may be brought by any person for injury sustained owing to neglect of the above precautions and to any such person or which may with the consent of the contractor be paid to compromise any claim by any such person.

Contractor to supply to plantladder scaffolding etc.

And is liable for damage arising for non-provision of light fencing etc.

Clause 18 :- No female labour shall be employed within the limits of contonment. The contractor shall not employ for the purpose of his contract any person who is below the age of twelve years and shall pay to each labour for the work done by such labourer wages not less than the wages paid for similar work in the neighbourhood.

Work not to be subject

The executive Engineer shall have the right to enquire into the case and decide any complaint alleging that the wages paid by the contractor to any labourer for the work done by such labour is less than the wages paid for similar work in the neighbourhood.

The officer in-charge of the work shall have the right to decide whether any labourer employed by contractor is below the age of twelve years and to refuse to allow any labourer whom he decided to be below the age of twelve years to be employed by the contractor.

Clause 19:- The Contractor shall not be assigned or subject without the written approval of the Executive Engineer. And if the contractor shall assign or subject his contract, or attempt so to do, or become insolvent proceedings to make any composition with his creditors or attempt so to do, or if any bribe, gratuity, gift loan, requisite, reward or advantage pecunairy of otherwise, shall either directly or indirectly be given promissed, or offered by the contractor, or any of his servant or agents to any public officer or person in the employ of Government in any way relating to his officer or employment or if any such officer or person shall become in any way directly or indirectly interested in the contract the Executive Engineer may there upon by notice in writing rescind the contract. The security deposit of the contractor shall there upon stand forfeited and be absolutely at the disposal of Government and the same consequence shall ensure as if the contract had been recinded under clause 3 here of, in addition the contractor shall not be entitled to recover or be paid to any work therefore actually performed the under the contract.

Contract may be resinded and security deposit forfelted for subletting bribes or if contractor become insolvant

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

लक्ष्मी देवी

such payable by way of compensation to be considered reasonable compensation without reference to actual loss

Clause 20:- All sums payable by way of compensation under any of these conditions shall be considered as reasonable compensation to be applied to the use of the Government without reference to the actual loss or damages sustained and there of not any damage shall have been sustained.

Clause 21 :- In the case of a sender by partners, any change in the constitution of the firm shall be forthwith notified by the contractor to the Engineer-in-charge or this information.

Charges in constitution of firm.

In case of failure to notify the change in the constitution within fifteen days the Engineer-in-charge may be notice in writing rescind the contract and the security deposit of the contractor shall thereupon stand forfeited and be absolutely at the disposal of Government and the same consequences shall ensure as if the contract has been rescinded under clause 3 hereof, and in addition the contractor shall not be entitled to recover or be paid for any work therefore actually performed under the contractor.

Works to be under direction of Suprintending Engineer

Clause 22 :- All work to be executed under the contract shall be executed under the direction and subject to the approval in all respect of the superintending Engineer of the circle for the time being who shall be entitled to direct at what point or points and in what manner they are to be commenced, and from time to time carried on.

Clause 23 :- In case any dispute or difference shall arise between the parties or either of there upon any question relating to the meaning of the specifications, designs drawings and instructions here before mentioned or as to the quality of workmanship or materials used on the work or as to the construction of any of the conditions or any clause or thing there in contained or as to any question, claim, rights of the parties, or any matter, or things whatsoever in any way arising out of or relating to the contract designs, drawings specifications, estimates, instruction order of these conditions or otherwise concerning the work or the execution, or failure to execute the same whether arising during the progress of the work of alter the completion or abondment thereof or as the breach of those contract then either party shall forthwith give to the order notice of such dispute or difference and such dispute or difference shall be referred to the Superintending Engineer of the circle and his decision there on shall be final, conclusive and binding on all the parties.

Lum sum in estimate

(a) Clause 24 :- When the estimate on which a tender is made includes lump sum in respect of the contract shall be entitled to payment in respect of the items or work involved of the work in question the same rates as are payable under this contract such terms, for if the part of the work in question is not in the opinion of the Engineer-in-charge, capable of measurement the Engineer-in-charge, may at his direction pay the lump sum amounts entered in the estimate, and the certificate in writing of the Engineer-in-charge shall be final and conclusive against the contractor with regard to any sum payable to him under the provision of this clause.

Action where no specificaiton.

Clause 25:- In the case of any class of work for which there is no such specification as is mentioned in rule 1, such work shall be carried out in accordance with the circle specification and in the event of there being no circle specification, then in such case the work shall be carried out in all respects in accordance with the instructions and requirements of the Engineer-in-charge.

Definition of works

Clause 26 :- The expression "work" or "works" where used in these conditions shall unless there be something either in the subject or context repugnant to such construction be constructed and taken to mean the work by or virtue of the contract contracted to be executed whether temporary or permanent, and whether original, altered substituted or additional.

Clause 27:- The terms and conditions of the agreement have been read/explained to me and.....certify.....clearly understand them

Witness.

Contractor.

Schedule XLV - Form No. 61

Schedule showing (Approximately) materials to be supplied, it available the rates of which they are to be charged for and the places at which they are to be supplied

Particulars	Rates at which the material will be charged to the contractor			Place of delivery
	Unit	Rs.	P.	

Note :-The person or firm submitting the tender should see that the rates in the above schedules are filled up by the Engineer-in-charge on the issue of the form prior to the submission of the tender.

(Signature of Contrator)

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

(Signature of Executive Engineer)

Bihar State Educational Infrastructure Development Corporation Ltd.

AGREEMENT for Construction of Additional Class Rooms (02 Unit) at Lekchhar Nirdeshak School Baruganiya, Block - Sikta, District - West Champaran (A.C.W. - 2410)

TENDER FOR WORKS

I/We hereby tender for the execution for the Governor of Bihar of the work specified in the under written memorandum at the rates specified therein within a period of 7 (seven) month from the date of written order to commence and in accordance in all respects with the specifications, drawing, and other documents referred to rule hereof and Subjects to the annexed condition of contract and with such materials as are provided for by and in other respects in accordance with such conditions so far as applicable.

MEMORANDUM

(A) Name of Work :- Construction of Additional Class Rooms (02 Unit) at Lekchhar Nirdeshak School Baruganiya, Block - Sikta, District - W. est Champaran, (A.C.W. - 2410)

(B) Estimated Cost :- Rs. 17,13,131=00
Agreement value :- Rs. 15,41,818=00

(C)Earnest Money :-

(D) Initial security deposits (including earnest money) to be deposited before the Commencement of the work:-

Earnest Money :- Rs. 81,000/- (Details attached)

(E) Percentage to be deducted from bill Rs. 5% (Rupees five percent)

(F) Time required for the work from date of written order to commence SIX MONTHS

(G) Date of written order to commence :-

(H) Total number of item of work tendered for :- 02

(a) If several sub-work are included they should be detailed in the separate list

(b) This deposit will be 5% of the estimated cost of the work

(c)This percentage deduction from bills will be credited to the contractors security deposits

BIHAR STATE CDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.
SHIKSHA BHAWAN, SAIDPUR, PATNA

BILL OF QUANTITIES FOR CONSTRUCTION OF ADDITIONAL CLASS ROOM.

THE ITEM RATE BASED ON S.O.R BCD BIHAR, DATE - 27.09.2018, & B.S.R (ELECTRICAL) 2018

	Group No.	Name Of School	Block		District	
	ACR-240	UCHHTAR MIDDLE SCHOOL BARGANIYA.	SIKTA		WEST CHAMPARAN	
	CIVIL WORKS					
Sl. No.	SOR Item No.	Item of Work	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	2	3	4	5	6.00	7.00
	EARTHWORK IN EXCAVATION					
1	2.8.1	Earthwork in excavation in as(exceeding 30cm in depth. 1.5m in width as well es 10sqm on plan) incloding dressing of sides and ramming of bottom,lift upto 1.5 including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m. All Kind of soil	75.358	cu.m	319.60	Rupees three hundred nineteen & paise sixty only.
2	2.29.1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5m All kinds of soil.	150.700	100 sqm	1126.90	Rupees one thousand one hundred twenty six & paise ninety only.
3	2.26	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth: consolidating each deposited layer by ramming and watering lead	55.100	cu.m	103.30	Rupees one hundred three & paise thirty only.
SAND FILLING						
4	2.28	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	52.300	cu.m	238.60	Rupees two hundred thirty eight & paise sixty only.
FLAT BRICK SOLING						
5	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	158.840	sq.m	277.50	Rupees two hundred seventy seven & paise fifty only.

Chief Engineer
B.S.E.I.D.C. Ltd. Patna

BIHAR STATE CHUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.
SHIKSHA BHAWAN, SAIDPUR PATNA

BILL OF QUANTITES FOR CONSTRUCTION OF ADDITIONAL CLASS ROOM

THE ITEM RATE BASED ON S.O.R RCD BIHAR, DATE - 22.09.2018. & B.S.R (ELECTRICAL) 2018

	Group No.	Name Of School	Block	District
	ACR-240	UCHHTAR MIDDLE SCHOOL BARGANIYA.	SIKTA	WEST CHAMPARAN
	CIVIL WORKS			

Sl. No.	SOR Item No.	Item of Work	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	2	3	4	5	6.00	7.00
		EARTHWORK IN EXCAVATION				
1	2.8.1	Earthwork in excavation in as(exceeding 30cm in depth 1.5m in width as well es 10sqm on plan) including dressing of sides and ramming of bottom,lift upto 1.5 including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m. All Kind of soil	75.358	cu.m	319.00	Rupees three hundred nineteen & paise sixty only.
2	2.29.1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish. lead upto 50 m and lift upto 1.5m All kinds of soil.	150.700	100 Sqm	1126.90	Rupees one thousand one hundred twenty six & paise ninety only
3	2.26	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and wetering lead	55.100	cu.m	103.30	Rupees one hundred three & paise thirty only
		SAND FILLING				
4	2.28	Supplying and Filling in plinth with local sand and under floors including watering, ramming consolidating and dressing complete.	52.700	cu.m	238.60	Rupees two hundred thirty eight & paise sixty only
		FLAT BRICK SOLING				
5	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of EI.	158.840	sq.m	277.50	Rupees two hundred seventy seven & paise fifty only.

	P.C.C.					
6	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level 1:3:6 (1cement: 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	3.509	cu.m	3461.40	Rupees three thousand four hundred sixty one & paise forty only.
7	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level 1:2:4 (1cement: 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	11.205	cu.m	4151.40	Rupees four thousand one hundred fifty one & paise thirty nine only.
	FLOORING & SKIRTING					
8	11.3 + 11.3.1	Cement concrete flooring 1:2:4(1 cement:2 coarse:sand:4 graded stone agregate) finished with a floating coat of neat cement including cement slurry, etc. but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	118.350	sq.m	282.60	Rupees two hundred eighty two & paise sixty only.
9	11.6.1	Cement plaster skirting (upto 30 cm hieght) with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement. 18 mm thick	10.471	sq.m	284.86	Rupees two hundred eighty four & paise eighty six only.
	R.C.C. WORK ABOVE PLINTH LVL.					
10	5.1.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing & reinforcement - all work upto plinth level. 1:1:2 (1cement: 1 coarse sand : graded stone aggregate 20mm nominal size)	14.697	cu.m	6434.40	Rupees six thousand four hundred thirty four & paise forty only.
11	5.2.1	Reinforced cement concrete work in wall (any thickness), including attached plasters, buttresses, plinth and struts etc upto floor five level excluding the cost of centring, shuttering, finishing & reinforcement - all work upto plinth level. 1:1:2 (1cement: 1 coarse sand : 2 graded stone aggregate 20mm nominal size)	6.297	cu.m	7255.40	Rupees seven thousand two hundred fifty five & paise forty only.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	P.C.C.					
6	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level 1:3:6 (1cement: 3 coarse sand : 6 grade stone aggregate 20mm nominal size)	3.509	cu.m	3161.40	Rupees three thousand four hundred sixty one & paise forty only.
7	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level 1:2:4 (1cement: 3 coarse sand : 6 grade stone aggregate 20mm nominal size)	11.205	cu.m	4151.40	Rupees four thousand one hundred fifty one & paise thirty nine only.
	FLOORING & SKIRTING					
8	11.3 + 11.3.1	Cement concrete flooring 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, etc. but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	118.350	sq.m	282.60	Rupees two hundred eighty two & paise sixty only.
9	11.6.1	Cement plaster skirting (upto 30 cm bieght) with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement. 18 mm thick	10.471	sq.m	284.80	Rupees two hundred eighty four & paise eighty six only.
	R.C.C. WORK ABOVE PLINTH LVL.					
10	5.1.1	Providing and laying in position specified grade of reinforced cemnat concrete excluding the cost of centring, shuttering, finishing & reinforcement - all work upto plinth level. 1:1:2 (1cement: 1 coarse sand : 1 graded stone aggregate 20mm nominal size)	14.597	cu.m	6134.40	Rupees six thousand four hundred thirty four & paise forty only.
11	5.2.1	Reinforced cement concrete work in wall (any thickness), including attached plastra, buttresses, plinth and sunts etc upto floor five level excluding the cost of centring, shuttering, finishing & reinforcement - all work upto plinth level. 1:1:2 (1cement: 1 coarse sand : 2 graded stone aggregate 20mm nominal size)	6.297	cu.m	7255.40	Rupees seven thousand two hundred fifty five & paise forty only.

12	5.3 + 5.33B.4 + 5.33B.1	Reinforced cement conrete work in beams,suspended floors, roofs having slope upto 15, landings,balconiec, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excludingthe cost of centring, shuttering, finishing and reinforement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size). Add or deduct for providing richer or leaner mixes respectively at all floor levels. Providing M-15grade R.C.C instead of M-20 grade R.C.C. Proiding M-25 grade R.C.C. instead of M-20 grade R.C.C.	21.871	cu.m	5917.30	Rupees five thousand nine hundred seventeen & paise thirty only.
	BRICK WORK					
13	6.1.14A	Brick work with bricks of class designation 100A in foundations and plinth in cement mortar 1:6 (1cement :6 coarse sand)	9.076	cu.m	4799.20	Rupees four thousand seven hundred ninety nine & paise twenty only.
14	6.1.14A + 6.3A	Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:6 (1 cement: 6 coarse sand) Extra for Brick work in superstructure above plinth level upto floor V cum	34.362	cu.m	5501.40	Rupees five thousand five hundred one & paise forty only.
	PLASTER WORK					
15	13.13.4	20 mm cement plaster of mix ; 1:6 (1 cement : 6 coarse sand)	233.225	sq.m	173.00	Rupees one hundred seventy three only.
16	13.11.4	12mm thick Cement plaster of mix 1:6 (1 cement : 6 coarse sand)	157.148	sq.m	126.20	Rupees one hundred twenty six & paise twenty only.
17	13.24.2	6mm thick Cement plaster of Ceiling mix 1:4 (1 cement : 4 coarse sand)	119.850	sq.m	110.90	Rupees one hundred ten & paise ninety only.
18	11.3.1 + 11.8	Cement concrete flooring 1:2:4(1 cement:2 coarse:sand:4 graded stone agregate) finished with a floating coat of neat cement including cement slurry, etc. but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate. Extra for making chequers of approved pattern on cement concrete floors, steps, landing, pavemerts etc.	116.988	sq.m	312.80	Rupees three hundred twelve & paise eighty only.

Chief Engineer
B.S.E.I.D.C. Ltd. Patna
07/08/19

12	5.3 + 5.33B.4 + 5.33B.1	Reinforced cement concrete work in beams,suspended floors, roofs having slope upto 15, lintels,balconies, shelves, chajjas, lintels bands, plain window sills, staircases and spiral stair cases upto floor five level excludingthe cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size) Add or deduct for providing richer or leaner mixes respectively at all floor levels Providing M-15grade R.C.C instead of M-20 grade R.C.C. Providing M-25 grade R.C.C instead of M-20 grade R.C.C.	21.871	cu.m	5912.20	Rupees five thousand nine hundred seventeen & paise thirty only.
	BRICK WORK					
13	6.1.14A	Brick work with bricks of class designation 100A in foundations and plinth in cement mortar 1:6 (1cement :6 coarse sand)	9.076	cu.m	4799.20	Rupees four thousand seven hundred ninety nine & paise twenty only.
14	6.1.14A + 6.3A	Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:6 (1 cement: 6 coarse sand) Extra for Brick work in superstructure above plinth level upto floor V cum	34.302	cu.m	8501.40	Rupees five thousand five hundred one & paise forty only.
	PLASTER WORK					
15	13.13.4	20 mm cement plaster of mix ; 1:6 (1 cement : 6 coarse sand)	233.225	sq.m	173.00	Rupees one hundred seventy three only.
16	13.11.4	12mm thick Cement plaster of mix 1:6 (1 cement : 6 coarse sand)	157.148	sq.m	126.20	Rupees one hundred twenty six & paise twenty only.
17	13.24.2	6mm thick Cement plaster of Ceiling mix 1:4 (1 cement : 4 coarse sand)	119.850	sq.m	110.90	Rupees one hundred ten & paise ninety only.
18	11.3.1 + 11.8	Cement concrete flooring 1:2:4(1 cement:2 coarse:sand:4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, etc. but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate. Extra for making chequers of approved pattern on cement concrete floors, steps, landing, pavements etc.	116.988	sq.m	312.80	Rupees three hundred twelve & paise eighty only

	FINISHING WORK					
19	13.77A.1	Distempering with 1st quality washable distemper (ready made) of approved manufacturer and of required shade and colour complete. As per manufacture's specifications. Two or more coats on new work	510.223	sq.m	46.50	Rupees forty six & paise fifty only.
20	13.80A.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth all complete as per building specification and direction of E/I,	0.000	sq.m	46.50	Rupees forty six & paise fifty only.
21	13.46 + 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	183.091	sq.m	89.40	Rupees eighty nine & paise forty only.
22	13.81.1	Applying priming coat with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and softwood)	24.192	sq.m	32.20	Rupees thirty two & paise twenty only.
23	13.81.3	Applying priming coat with ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel work.	18.000	sq.m	27.50	Rupees twenty seven & paise fifty only.
24	13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coats on new work	42.190	sq.m	70.40	Rupees seventy & paise forty only.
25	10.1	Structural steel work in singal section fixed without connecting plate including cutting.hoisting,fixing in position and applying a priming coat of approved steel primer all complete.	96.600	Kg.	68.20	Rupees sixty eight & paise twenty only.
26	9.21.1	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) NON decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including stainless steel butt hinges with necessary screws-	8.820	sq.m	1602.70	Rupees one thousand six hundred two & paise seventy only.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	FINISHING WORK					
19	13.77A.1	Distempering with 1st quality washable distemper (ready made) of approved manufacturer and of required shade and colour complete. As per manufacturer's specifications Two or more coats on new work	510.223	sq.m	46.50	Rupees forty six & paise fifty only.
20	13.80A.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth all complete as per building specification and direction of EI.	0.000	sq.m	46.50	Rupees forty six & paise fifty only.
21	13.46 + 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	183.091	sq.m	89.40	Rupees eighty nine & paise forty only
22	13.81.1	Applying priming coat with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and softwood)	24.192	sq.m	32.20	Rupees thirty two & paise twenty only.
23	13.81.3	Applying priming coat with ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel work.	18.000	sq.m	27.50	Rupees twenty seven & paise fifty only.
24	13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coats on new work	12.190	sq.m	70.40	Rupees seventy & paise forty only.
25	10.1	Structural steel work in singal section fixed without connecting plate including cutting,hoisting,fixing in position and applying a priming coat of approved steel primer all complete.	06.600	Kg	68.20	Rupees sixty eight & paise twenty only.
26	9.21.1	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) NON decorative type, core of block board construction with frame of I st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including stainless steel butt hinges with necessary screws-	8.820	sq.m	1002.70	Rupees one thousand six hundred two & paise seventy only.

	STEEL WORK					
27	10.12.1 + 10.13B	Providing and fixing glazed steel doors, windows or ventilators of standard rolled steel sections, joints mitered and welded with 15x3 mm M.S. lugs10cm long with steel legs embedded in cement concrete blocks 15x10x10cm.of (1:3:6) (1cement : 3coarse sand : 6graded stone aggregate 20mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of glass panels with glazing clips and special metal-sash putty of approved make complete including applying a priming coat of approved steel primer excluding the cost of metal beading and other fitting except necessary hinges or pivots as required Extra for providing and fixing steel beading of approved shape and section with screws instread of glaxing clips and met. Sash putty in steel doors, windows,ventilators and composite units.	18.000	sq.m	3340.30	Rupees three thousand three hundred forty & paise thirty only.
28	9.48.1	Providing and fixing M.S. grills of requirement pattern in frames of windows etc. with M.S. flats square or round bars etc all complete fixed to steel windows by welding.	234.000	Kgs.	114.20	Rupees one hundred fourteen & paise twenty only.
29	B.C.D. 10.32.1	Steel work welded in built up sections/framed work including cutting hoisting, rixing in position and applying a priming coat of approved steel primer using structural steel, etc. as required. all complete as per building specification and direction of E/l,	0.000	Kgs.	75.50	Rupees seventy five & paise fifty only.
30	10.38.2	Providing & fixing glass panes with putty and glazing clips in stee doors, windows, clerestory windows all complete with. 5.5 mm thick glass panes.	1.260	sq.m	1027.80	Rupees one thousand twenty seven & paise eighty only.
31	9.63.1	Providing and fixing oxidised M.S.tower bolt black finish,(barrel type) with necessary screws etc.complete 250x10mm	4.000	each	67.20	Rupees sixty seven & paise twenty only.
32	9.66.1	Providing and fixing ISI marked oxidised M.S. handles conforming to IS :4992 with necessary screws etc. complete: 125 mm	4.000	each	29.90	Rupees twenty nine & paise ninety only.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	STEEL WORK					
27	10.12.1 + 10.13B	Providing and fixing glazed steel doors, windows or ventilators of standard rolled steel sections, joints mitered and welded with 15x3 mm M.S. lugs10cm long with steel, legs embedded in cement concrete blocks 15x10x10cm.of(1:3:6) (1cement : 3coarse sand : 6graded stone aggregate 20mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of glass panels with glazing clips and special metal-sash putty of approved make complete including applying a priming coat of approved steel primer excluding the cost of metal beading and other fitting except necessary hinges or pivots as required Extra for providing and fixing steel beading of approved shape and section with screws instead of glazing clips and met. Sash putty in steel doors, windows,ventilators and composite units.	18.000	sq.m	3340.30	Rupees three thousand three hundred forty & paise thirty only.
28	9.48.1	Providing and fixing M.S. grills of requirement pattern in frames of windows etc. with M.S. flats square or round bars etc all complete fixed to steel windows by welding.	234.000	Kgs.	114.20	Rupees one hundred fourteen & paise twenty only.
29	B.C.D. 10.32.1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel, etc. as required, all complete as per building specification and direction of EN.	0.000	Kgs.	75.50	Rupees seventy five & paise fifty only
30	10.38.2	Providing & fixing glass panes with putty and glazing clips in size doors, windows, clerestory windows all complete with, 5.5 mm thick glass panes.	1.260	sq.m	1027.80	Rupees one thousand twenty seven & paise eighty only
31	9.63.1	Providing and fixing oxidised M.S.tower bolt black finish,(Barrel type) with necessary screws etc.complete 250x10mm	4.000	each	67.20	Rupees sixty seven & paise twenty only
32	9.66.1	Providing and fixing ISI marked oxidised M.S. handles conforming to IS :1092 with necessary screws etc. complete: 125 mm	4.000	each	29.90	Rupees twenty nine & paise ninety only

33	9.101.2	Providing and fixing alluminium hanging floor door stopper anodised (anodic coating not less than grade AC 10 as per IS :1868) transparent or dyed to required colour and shade with necessary screws etc.complete:Twin rubber stopper	4.000	each	40.40	Rupees forty & paise forty only.
34	9.62.1	Providing and fixing M.S. sliding door bolts bright finished or/and black enamelled,with nuts and screws etc.compelled: 300x16 mm	4.000	each	162.40	Rupees one hundred sixty two & paise forty only.
35	5.22	Reinforcement for RCC work including straightening, cutting, bending, placing in position and bonding all complete.				
		TMTC-500				
	5.22.1	Mild steel 6.00 mm dia	15.00	KG	76.10	Rupees seventy six & paise ten only.
	5.22.7A	TMTC-500 8mm dia	542.000	KG	77.40	Rupees seventy seven & paise forty only.
	5.22.7B	TMTC-500 10mm dia	270.000	KG	76.70	Rupees seventy six & paise seventy only.
	5.22.7C	TMTC-500 12mm dia	786.000	KG	75.20	Rupees seventy five & paise twenty only.
	5.22.7D	TMT-500 16mm dia	272.000	KG	76.00	Rupees seventy six only.
	5.22.7E	TMT-500 20mm dia	45.000	KG	76.00	Rupees seventy six only.
	5.22.7F	TMT-500 25mm dia	0.000	KG	76.00	Rupees seventy six only.
36	10.17	Providing and fixing M.S.fan clamp type I or II of 16 mm dia.M.S. bar bent to shape with hooked ends in R.C.C slabs during laying including painting the exposed portion of loop,all as per standard design complete.	8.000	Each	137.70	Rupees one hundred thirty seven & paise seventy only.
	MISCELLANEOUS WORK					
37	4.17	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20mm nominal size) over 75mm bad by dry brick ballast 40mm nominal size well rammend and consolidated and grouted with fine sand including finishing the top smooth.	20.520	sq.m	417.60	Rupees four hundred seventeen & paise sixty only.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

33	9.101.2	Providing and fixing aluminium hanging floor door stopper anodised (anodic coating not less than grade AC 10 as per IS :1868) transparent or dyed to required colour and shade with necessary screws etc.complete:Twin rubber stopper	4.000	each	40.40	Rupees forty & paise forty only.
34	9.62.1	Providing and fixing M.S. sliding door bolts bright finished or/and black enamelled with nuts and screws etc.complelted: 300x16 mm	4.000	each	162.40	Rupees one hundred sixty two & paise forty only.
35	5.22	Reinforcement for RCC work including straightening, cutting, bending, placing in position and bonding all complete.				
		TMTC-500				
	5.22.1	Mild steel 6.00 mm dia	15.00	KG	76.10	Rupees seventy six & paise ten only.
	5.22.7A	TMTC-500 8mm dia	542.000	KG	77.40	Rupees seventy seven & paise forty only.
	5.22.7B	TMTC-500 10mm dia	270.000	KG	76.70	Rupees seventy six & paise seventy only.
	5.22.7C	TMTC-500 12mm dia	786.000	KG	75.20	Rupees seventy five & paise twenty only.
	5.22.7D	TMT-500 16mm dia	272.000	KG	76.00	Rupees seventy six only.
	5.22.7E	TMT-500 20mm dia	45.000	KG	76.00	Rupees seventy six only.
	5.22.7F	TMT-500 25mm dia	0.000	KG	76.00	Rupees seventy six only.
36	10.17	Providing and fixing M.S.fan clamp type I or II of 16 mm dia.M.S. bar bent to shape with hooked ends in R.C.C slabs during laying including painting the exposed portion of loop,all as per standard design complete.	8.000	Each	137.70	Rupees one hundred thirty seven & paise seventy only.
		MISCELLANEOUS WORK				
37	4.17	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 20mm nominal size) over 75mm bed by dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth.	20.520	sq.m	417.60	Rupees four hundred seventeen & paise sixty only.

	SHUTTERING					
38	5.9.1	Centring and shuttering including strutting, propping etc. and removal of form for foundation, footings, basees of columns etc. for mass concrete.	22.080	Sqm.	186.30	Rupees one hundred eighty six & paise thirty only.
39	5.9.5	Centring and shuttering including strutting, propping etc. and removal of form for lintel, beams, plinth beams, griders, bressumers and contilevers.	88.275	Sqm.	335.30	Rupees three hundred thirty five & paise thirty only.
40	5.9.6	Centring and shuttering including strutting, propping etc. and removal of form for columns, pillars, piers, abutments, posts and struts	35.625	Sqm.	425.80	Rupees four hundred twenty five & paise eighty only.
41	5.9.3	Centring and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform.	55.030	Sqm.	362.60	Rupees three hundred sixty two & paise sixty only.
42	12.39	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 mx1 mx400 micron, finished 12 mm cement plaster 1:3 (1 cement:3 coarse sand) and a coat of neat cement rounding the edges and making and finishing the outlet complete	2.000	nos	172.30	Rupees one hundred seventy two & paise thirty only.
					Total (A)	**1,175,710.72**
43	***CARRIAGE OF MATERIALS***					
	Lead in Km	Type of materials			**Rate Incl. 1% Lab. Cess**	
	5	Cement	42.850	MT	328.25	Rupees three hundred twenty eight & paise twenty five only.
	187	Sand	60.170	cum	3035.43	Rupees three thousand thirty five & paise forty three only.
	3	Local Sand	52.300	cum	262.05	Rupees two hundred sixty two & paise five only.
	458	Stone Chips	73.320	cum	2511.57	Rupees two thousand five hundred eleven & paise fifty seven only.

Chief Engineer
B.S.E.I.D.C. Ltd. Patna

	SHUTTERING					
38	5.9.1	Centring and shuttering including strutting, propping etc. and removal of form for foundation, footings, bases of columns etc. for mass concrete	22.050	Sqm.	180.30	Rupees one hundred eighty six & paise thirty only.
39	5.9.5	Centring and shuttering including strutting, propping etc. and removal of form for lintel, beams, plinth beams, girders, bressumers and cantilevers.	88.275	Sqm.	334.30	Rupees three hundred thirty five & paise thirty only.
40	5.9.6	Centring and shuttering including strutting, propping etc. and removal of form for columns, pillars, piers, abutments, posts and struts	35.625	Sqm.	425.80	Rupees four hundred twenty five & paise eighty only.
41	5.9.3	Centring and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform.	55.030	Sqm.	362.90	Rupees three hundred sixty two & paise sixty only.
42	12.39	Making kiltras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 mx1 mx400 micron, finished 12 mm cement plaster 1:3 (1 cement:3 coarse sand) and a coat of neat cement rounding the edges and making and finishing the outlet complete	2.000	nos	172.30	Rupees one hundred seventy two & paise thirty only.
				Total (A)		1,125,710.72
43	CHARGES OF MATERIALS					
	Lead in Km	Type of materials			Rate incl. 17% Lab. Cess	
	5	Cement	42.850	MT	398.25	Rupees three hundred twenty eight & paise twenty five only.
	187	Sand	60.170	cum	3035.45	Rupees three thousand thirty five & paise forty three only
	3	Local Sand	52.300	cum	262.05	Rupees two hundred sixty two & paise five only.
	458	Stone Chips	73.320	cum	2511.57	Rupees two thousand five hundred eleven & paise fifty seven only.

	8	Brick	26.586	Thous.	767.08	Rupees seven hundred sixty seven & paise eight only.
	5	Steel	1.930	MT	328.25	Rupees three hundred twenty eight & paise twenty five only.
44	**DIFF. IN COST OF METERIAL AS PER BCD SOR EFF. FROM 27.09.2018 ONLY**					
	Bricks		26.586	Thous.	332.19	Rupees three hundred thirty two & paise nineteen only.
	Cement		42.850	MT	318.16	Rupees three hundred eighteen & paise sixteen only.
					Total (B)	**438,052.73**
		ELECTRICAL				
45	1.1	Point Wiring in PVC Conduit, with piano type Switch:-				
		Wiring for light point /fan point / exhaust fan point / call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.				
	1.1.3	Group C	26	Nos.	681.00	Rupees six hundred eighty one only.
46	1.29	Supplying and fixing metal box of 150mm X 75mm X 60mm deep(nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings).	5	Each	187.00	Rupees one hundred eighty seven only.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	8	Brick	26.580	Thous.	767.08	Rupees seven hundred sixty seven & paise eight only.
	9	Steel	1.930	MT	328.25	Rupees three hundred twenty eight & paise twenty five only
44		DIFF. IN COST OF METERIAL AS PER BCD SOR EFF. FROM 27.09.2018 ONLY				
		Bricks	26.580	Thous.	332.19	Rupees three hundred thirty two & paise nineteen only
		Cement	42.850	MT	318.16	Rupees three hundred eighteen & paise sixteen only
				Total (B)		438,052.73
		EXTRA				
45	1.1	Point Wiring in PVC Conduit, with piano type Switch:-				
		Wiring for light point /fan point/ exhaust fan point / call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FR1.5 PVC insulated copper conductor single core cable etc. as required.				
	1.1.3	Group C	26	Nos	631.00	Rupees six hundred eighty one only.
46	1.29	Supplying and fixing metal box of 150mm X 75mm X 60mm deep(nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings).	5	Each	187.00	Rupees one hundred eighty seven only.

	1.3	Supply and Fixing Light Plug Point with piano type Accessories:-				
47		Supplying and fixing metal box of 180mm x 100mm x 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	1	Nos.	286.00	Rupees two hundred eighty six only.
48	1.7.2	2x2.5 Sqmm + 1x2.5 sq mm earth wire	98	Mtrs.	161.00	Rupees one hundred sixty one only.
	1.5	Power Plug Wiring in PVC conduit (2x4 sq. mm):-				
49		Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed mediumclass PVC conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required	18	Mtrs.	200.00	Rupees two hundred only.
	1.23	Supplying and fixing following piano type switch/ socket on the existing switch box / cover including connections etc.as required				
50	1.23.1	5/6 amps switch.	5	Each	39.00	Rupees thirty nine only.
	1.23.4	3 pin, 5/6 amps socket outlet.	2	Each	52.00	Rupees fifty two only.
	1.15	Circuit / Sub-main wiring in PVC Conduit:-				
51		Wiring for circuit / sub-main wiring along with earth wire with the following sizes of PVC insulated, copper conductor, single core cable in surface/recessed PVC conduit as required.				
	1.15.29+1.15.31	4x6.0 Sqmm + 2x6.0 sqmm earth wire (to be used as sub main)	21	Mtrs.	400.00	Rupees four hundred only.
	2.12	S/F 'C' series SP MCB:-				
52		Supplying and fixing 240 volts, 'C' series, miniature circuit breaker suitable for inductive loads of following poles in the existing MCB DB complete with connections, testing and commissioning etc, as required.				

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	1.3	Supply and Fixing Light Plug Point with piano type Accessories-				
47		Supplying and fixing metal box of 150mm x 100mm x 60mm deep (nominal size) or surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	1	Nos.	286.00	Rupees two hundred eighty six only
48	1.7.2	2x2.5 Sqmm + 1x2.5 sq mm earth wire	98	Mtrs.	161.00	Rupees one hundred sixty one only
49	1.5	Power Plug Wiring in PVC conduit (2x4 sq mm):-				
		Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	18	Mtrs.	200.00	Rupees two hundred only.
50	1.23	Supplying and fixing following piano type switch/ socket on the existing switch box / cover including connections etc.as required				
	1.23.1	5/6 amps switch.	5	Each	39.00	Rupees thirty nine only.
	1.23.4	3 pin, 5/6 amps socket outlet.	2	Each	52.00	Rupees fifty two only.
51	1.15	Circuit / Sub-main wiring in PVC Conduit:-				
		Wiring for circuit / sub-main wiring along with earth wire with the following sizes of PVC insulated, copper conductor, single core cable in surface/recessed PVC conduit as required				
	1.15.29+1 :15.31	4x6.0 Sqmm + 2x6.0 sqmm earth wire (to be used as sub main)	21	Mtrs.	400.00	Rupees four hundred only
52	2.12	S/F 'C' series SP MCB:-				
		Supplying and fixing 240 volts, 'C' series, miniature circuit breaker suitable for inductive loads of following poles in the existing MCB DB complete with connections, testing and commissioning etc, as required.				

	2.12.1	6/32A, Single Pole	1	Each	192.00	Rupees one hundred ninety two only.
53	2.13	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	2.13.2	40 Amp.	1	Each	805.00	Rupees eight hundred five only.
54	2.9.4	S/F TP MCB DB:-				
		Supplying and fixing of following way,horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (Without MCB/RCCB/ISOLATOR). Make :- Legrand/Anchor/Havells/HPL.				
	2.9.4	4 Ways (4+12 ways) double door	1	Set	2388.00	Rupees two thousand three hundred eighty eight only.
55	1.33	S/F Ceiling Rose:-				
		Supplying and fixing 2 pin ceiling rose on the existing junction box/ wooden block including connection etc as required.	12	Each	42.00	Rupees forty two only.
56	1.34	S/F Batten / Angle Holder:-				
		Supplying and fixing batten / angle holder including connection etc as required.	8	Each	46.00	Rupees forty six only.
57	1.25	S/F Modular type electronic fan regulator:-				
		Supplying and fixing stepped type fan regulator on the existing modular plate switch box including connections but excluding modular plate etc as required.	8	Each	359.00	Rupees three hundred fifty nine only.
		EARTHING				
58	3.5	COPPER EARTH PLATE ELECTRODE:-				
		Earthing with copper earth plate 600mmx 600mmx 3mm thick including acessories and providing masonary enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc with charcoal/cock and salt as required.	1	Each	10341.00	Rupees ten thousand three hundred forty one only.

लक्ष्मी देवी

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

	2.12.1	6/32A, Single Pole	1	Each	192.00	Rupees one hundred ninety two only.
53	2.13	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	2.13.2	40 Amp.	1	Each	805.00	Rupees eight hundred five only
54	2.9.4	S/F TP MCB DB:-				
		Supplying and fixing of following way,horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required (Without MCB/RCCB/ISOLATOR). Make :- Legrand/Anchor/Havells/HPL.				
	2.9.4	4 Ways (4+12 ways) double door	1	Set	2388.00	Rupees two thousand three hundred eighty eight only.
55	1.33	S/F Ceiling Rose:-				
		Supplying and fixing 2 pin ceiling rose on the existing junction box/ wooden block including connection etc as required.	12	Each	42.00	Rupees forty two only.
56	1.34	S/F Batten / Angle Holder:-				
		Supplying and fixing batten / angle holder including connection etc as required	8	Each	46.00	Rupees forty six only.
57	1.25	S/F Modular type electronic fan regulator:-				
		Supplying and fixing stepped type fan regulator on the existing modular plate switch box including connections but excluding modular plate etc as required.	8	Each	350.00	Rupees three hundred fifty nine only.
		EARTHING				
58	3.5	COPPER EARTH PLATE ELECTRODE:-				
		Earthing with copper earth plate 600mmx 600mmx 3mm thick including accessories and providing masonary enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/cock and salt, as required.	1	Each	1034.00	Rupees ten thousand three hundred forty one only.

59	3.8	Supplying and laying 25 mm X 5 mm copper strip at 0.50 metre below ground as strip earth electrode, including connection/terminating with nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of brass nut bolt & spring washer spaced at 50mm)	15	Mtrs.	898.00	Rupees eight hundred ninety eight only.
60	3.14	P/F 25 x 5 mm copper earth strip in surface/ recess :-				
		Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	12	Mtrs.	1032.00	Rupees one thousand thirty two only.
61	2.3	S/F HRC fuse type TP&N switch disconnector:- Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required.				
	2.3.2	63 amps,TP&N, HRC	0	Each	2124.00	Rupees two thousand one hundred twenty four only.
	2.3.1	32 amps,TP&N, HRC	1	Each	1490.00	Rupees one thousand four hundred ninety only.
					Total (C)	**91,818.00**
		Fire Fighting				
62	DGS&D	Brand new ISI marked Life Guard ABC type multipurpose Fire Extinguishers 4 Kgs. Capacity, fitted with pressure guage complete in all respects, ready to use, complete installation kit.	1	set.	7549.75	Rupees seven thousand five hundred forty nine & paise seventy five only.
						7,549.75
					Grand Total (A+B+C+D)	**1,713,131.20**
					Say	**1,713,131.00**

(Rupees Seventeen Lac Thirteen Thousand One Hundred Thirty-One Only)

Tender approved in favour of Lakshmi Devi @ 10.00% (Ten Decimal Zero Zero Percent) below BOQ Rate i.e. total amount comes to Rs. 15,41,818=00 (Rupees Fifteen Lacs Forty One Thousand Eight Hundred Eighteen Only)

लक्ष्मी देवी

Chief Engineer
B.S.E.I.D.C. Ltd. Patna

59	3.8	Supplying and laying 25 mm X 5 mm copper strip at 0.50 mtrs below ground as strip earth electrode, including connection/terminating with nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of brass nut bolt & spring washer spaced at 50mm)	15	Mtrs	898.00	Rupees eight hundred ninety eight only.
60	3.14	P/F 25 x 5 mm copper earth strip in surface/ recess :-				
		Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required	12	Mtrs.	1032.00	Rupees one thousand thirty two only.
61	2.3	S/F HRC fuse type TP&N switch disconnector- Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections etc. as required.				
	2.3.2	63 amps,TP&N, HRC	0	Each	2124.00	Rupees two thousand one hundred twenty four only
	2.3.1	32 amps,TP&N, HRC	1	Each	1490.00	Rupees one thousand four hundred ninety only.
				Total (C)		91,813.00
		Fire Fighting				
62	DOS&D	Brand new ISI marked Life Guard ABC type multipurpose Fire Extinguishers 4 Kgs. Capacity, fitted with pressure guage complete in all respects, ready to use, complete installation kit.	1	set	7549.75	Rupees seven thousand five hundred forty nine & paise ses enty five only.
					7,549.75	
				Grand Total (A+B+C+D)		1,713,131.28
				Say		1,713,131.00

(Rupees Seventeen Lac Thirteen Thousand One Hundred Thirty-One Only)

Tender approved in favour of Lakshmi Devi @ 10.00% (Ten Decimal Zero Zero Percent) below BOQ Rate i.e. total amount comes to Rs. 15,41,818=00 (Rupees Fifteen Lacs Forty One Thousand Eight Hundred Eighteen Only)

Performance Security

Name of Agency:- "Lakshmi Devi"

Performance Security of Regarding " Construction of **Additional Class Room at Uchchtar Madhyamik Vidyalaya , Bargania, Block Sikta, Bettiah,** (NIT-90/17-18, SL No. -09)

FDR /TD/B.G. No.	D.O.I		AMOUNT
3652954196	15.05.17		39,000.00
3509099193	06.02.19		22,000.00
46 EF 334692	16.02.15		10,000.00
30 EF 463583	28.11.14		10,000.00
		Total-	81,000.00

(Rupees Eighty One Thousand only)

Amit Kr. Sam 30/7/19
लेखा पदाधिकारी
बिहार राज्य शैक्षणिक आधारभूत संरचना
विकास निगम लि०, पटना

30/7/19

लक्ष्मी देवी

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

7/8

विहार सरकार

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड
BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. of Bihar Undertaking)
ISO 9001:14001; OHSAS 18001
Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna - 800 004
Tel. No. : 0612 - 2660850 • Fax No. : 0612 - 2660256
E-mail : bseidc@gmail.com • Website : http://www.bseidc.in • CIN : U80301BR2010SGC015859

Letter of Acceptance

पत्रांकः– BSEIDC/FIN/3519/2018-19/– 1598 पटना, दिनांक 08.03.19

सेवा में,

Lakshmi Devi
Vill-Sarasawa, Po-Bakulahar Math, Ps- Gopalpur,
West Champaran, Mob-9430036366

विषयः– बिहार राज्य अंतर्गत " **Construction of Additional Class Room at Uchchtar Madhyamik Vidyalaya, Bargania, Block-Sikta, Distt.- Pashchim Champaran, (ACR-240),N.I.T. No.-90/(2018-19),Sl. No.: 09** हेतु **Performance Security** जमा कर एकरारनामा करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि विषयांकित कार्य हेतु आपके द्वारा उद्धृत दर BOQ से 10% कम यानि कुल राशि **रू० 15,41,818/–(पन्द्रह लाख एकतालीस हजार आठ सौ अठारह रूपये)** मात्र पर आपके पक्ष में निविदा की स्वीकृति प्रदान की गई है।

अतः निदेश दिया जाता है कि उक्त कार्य के एकरारनामा हेतु Performance Security की राशि **रू० 78,000/– (अठहतर हजार रूपये)** मात्र का पोस्ट ऑफिस सावधि जमा पासबुक/1, 2, 3 वर्षीय पोस्ट ऑफिस टाईम डिपोजिट/राष्ट्रीय बचत प्रमाण पत्र/किसान विकास पत्र, जो प्रबंध निदेशक, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०, पटना के नाम से प्रतिज्ञिप्त (Pledged) हो अथवा फिक्सड डिपोजिट रसीद जो बिहार राज्य में स्थित Nationalized/Scheduled बैंक से निर्गत हो एवं प्रबंध निदेशक, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि० पटना के नाम से प्रतिज्ञिप्त (Pledged) हो, जमा कर एकरारनामा कर लें।

कार्य हित में यह निदेश दिया जाता है कि आप तत्काल संबंधित कार्यपालक अभियंता से संपर्क कर कार्य प्रारंभ करें। इस पत्र की निर्गत की तिथि को कार्य प्रारंभ की तिथि माना जाएगा। Performance Security की राशि के सत्यांपन के उपरांत एकरारनामा किया जाएगा।

विश्वासभाजन

08/03/19
मुख्य अभियंता

ज्ञापांक : BSEIDC/FIN/3519/2018-19/– 1598 पटना, दिनांक 08.03.19

प्रतिलिपि :Sri Pankaj Kumar Singh, Computer Programmer for uploading on BSEIDC website/Senior Account Officer/ All Executive Engineer/ Suprintending Engineer BSEIDC for information & necessary action.

08/03/19
Chief Engineer
B.S.E.I.D.C. Ltd, Patna

08/03/19
मुख्य अभियंता

बिहार सरकार

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड
BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. of Bihar Undertaking)
ISO 9001:14001; OHSAS 18001
Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna - 800 004
Tel. No. : 0612 - 2660850 • Fax No. : 0612 - 2660256
E-mail : bseidc@gmail.com • Website : http://www.bseidc.in • CIN : U80301BR2010SGC015859

Letter No-BSEIDC/NIT/2018-19/- 093 Date:- 04/01/2019

शुद्धि–पत्र–02

इस कार्यालय के पुनर्निविदा आमंत्रण सूचना सं०–90, वर्ष 2018–19 through e-tendering website: www.eproc.bihar.gov.in/www.bseidc.in के **क्रम सं०– 01 से 05** पर अंकित कार्य की निविदा को अपरिहार्य कारणवश रद्द किया जाता है।

04/01/19
मुख्य अभियंता
04-1-19 04/1/19

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

बिहार सरकार

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड
BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. of Bihar Undertaking)
ISO 9001:14001; OHSAS 18001
Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna - 800 004
Tel. No. : 0612 - 2660850 • Fax No. : 0612 - 2660256
E-mail : bseidc@gmail.com • Website : http://www.bseidc.in • CIN : U80301BR2010SGC015859

Letter No-BSEIDC/NIT/2018-19/- ४३७० Date:- २७.१२.१८

शुद्धि–पत्र–1

इस कार्यालय के पुनर्निविदा आमंत्रण सूचना सं०–90, वर्ष 2018–19 through e-tendering website: www.eproc.bihar.gov.in/bseidc.in के **क्रम सं०–01 से 05** एवं **क्रम सं०– 07 से 08** पर अंकित कार्यो के लिए यह **पुनर्निविदा** नही है, बल्कि प्रथम बार प्राप्त की जाने वाली **निविदा** है।

27.12.18
मुख्य अभियंता

27.12.18 27/12/18

सरिता देवी

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

बिहार सरकार

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड
BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. of Bihar Undertaking)
ISO 9001:14001; OHSAS 18001
Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna - 800 004
Tel. No. : 0612 - 2660850 • Fax No. : 0612 - 2660256
E-mail : bseidc@gmail.com • Website : http://www.bseidc.in • CIN : U80301BR2010SGC015859

पुनर्निविदा आमंत्रण सूचना सं०–90 वर्ष 2018–19

प्रतिशत दर निविदा **(F2 Single Bid)**

(केवल ई–टेन्डरिंग पद्धति के अनुसार वेबसाइट www.eproc.bihar.gov.inपर)

बिहार राज्य अंतर्गत विभिन्न विद्यालयों में **अतिरिक्त वर्ग कक्ष (ACR)** के भवनों के निर्माण कार्य हेतु प्रतिशत दर निविदा आमंत्रित की जाती हैं। इस निविदा में संबंधित जिला में निबंधित सिर्फ स्थानीय अभिकर्त्ता (श्रेणी–4) संवेदक ही भाग ले सकते हैं।

क्रम सं०	ग्रुप का नाम	जिला का नाम	प्रखण्ड का नाम	विद्यालय का नाम	इकाई	प्राक्कलित राशि (लाख रू० में)	अग्रधन की राशि (लाख रू० में)	परिमाण विपत्र का मूल्य (रू०में)	Beltron Bid Processing Fee (In Rs.)	कार्य समाप्ति की अवधि
1	ACR-223	अररिया	अररिया	उत्क्रमित माध्यमिक विद्यालय, पैकटोला (गर्ल्स कॉमन रूम शौचालय सहित)	1	14.00	0.28	5,000/-	As appeared on e-tendering website	06माह
2	ACR-224	अररिया	अररिया	उत्क्रमित माध्यमिक विद्यालय, गैयारी (गर्ल्स कॉमन रूम शौचालय सहित)	1	14.00	0.28	5,000/-	As appeared on e-tendering website	06 माह
3	ACR-225	अररिया	अररिया	उत्क्रमित माध्यमिक विद्यालय, अररिया बस्ती (गर्ल्स कॉमन रूम शौचालय सहित)	1	14.00	0.28	5,000/-	As appeared on e-tendering website	06माह
4	ACR-226	अररिया	अररिया	उत्क्रमित माध्यमिक विद्यालय, बलवात (गर्ल्स कॉमन रूम शौचालय सहित)	1	14.00	0.28	5,000/-	As appeared on e-tendering website	06माह
5	ACR-227	अररिया	अररिया	उच्च विद्यालय, पटेगना पलासी (गर्ल्स कॉमन रूम शौचालय सहित)	1	14.00	0.28	5,000/-	As appeared on e-tendering website	06माह
6	ACR-234	मधुबनी	रहिका	नागेन्द्र झा बालिका उच्च विद्यालय, बसौली	3	20.64	0.413	5,000/-	As appeared on e-tendering website	06माह
7	ACR-238	रोहतास	सासाराम (एम)	उ०म०(+2) विद्यालय रामेश्वरगंज	2	13.40	0.27	5,000/-	As appeared on e-tendering website	06माह
8	ACR-239	रोहतास	सासाराम (एम)	रमा जैन बा०उ०वि०(+2)	2	13.40	0.27	5,000/-	As appeared on e-tendering website	06माह
9	ACR-240	पश्चिमी चम्पारण	सिकटा	उच्चतर माध्यमिक विद्यालय बरगनिया	2	13.40	0.27	5,000/-	As appeared on e-tendering website	06माह
10	ACR-241	पश्चिमी चम्पारण	सिकटा	उच्चतर माध्यमिक विद्यालय पुरनिया	2	13.40	0.27	5,000/-	As appeared on e-tendering website	06माह

लक्ष्मी देवी

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

नोट:–(i) प्राक्कलित राशि घट या बढ़ सकती है एवं तद्नुसार अग्रधन की राशि घट या बढ़ सकती है।
(ii) वेबसाईट:**www.eproc.bihar.gov.in** पर अंकित प्राक्कलित राशि, अग्रधन की राशि एवं परिमाण विपत्र की राशि अंतिम रुप से मान्य होगा।

(1) विज्ञापन निर्गत करने की तिथि :– दिनांक:–13.12.2018
(2) परिमाण विपत्र प्राप्त करने(डाउनलोड) की अवधि एव समय :– दिनांक– 04.01.2019 से 13.01.2019 15:00 घंटा तक (वेबसाईट:**www.eproc.bihar.gov.in** पर)
(3) निविदा प्राप्ति (अपलोड) की अंतिम तिथि एवं समय :– दिनांक– 14.01.2019, समय– 15:00 घंटा तक
(4) अग्रधन जमा करने की अंतिम तिथि एवं समय :– दिनांक– 15.01.2019 (अवकाश घोषित होने पर अगला कार्य दिवस), समय– 15:00 घंटा तक
(5) निविदा खोलने की तिथि एवं समय :– दिनांक– 15.01.2019, समय– 16:30 घंटा तक (वेबसाईट–**www.eproc.bihar.gov.in**पर)
(6) निविदा खोलने का स्थान :– वेबसाईट–**www.eproc.bihar.gov.in**पर
(7) निविदा की वैधता की अवधि :– 120 दिन

(8) ई–टेन्डरिंग की प्रकिया मे भाग लेने हेतु संवेदकों को पंजीकृत होना होगा, जिससे कि उन्हें उपयोगकर्ता का नाम **(user ID)** पासवर्ड **(Password)** अंकीय हस्ताक्षर **(Digital Signature)** निर्गत की जायेगी। यह उन्हे वेबसाईट **www.eproc.bihar.gov.in** से डाउनलोड करने/टेन्डर की प्रक्रिया में भाग लेने की योग्यता प्रदान करेगा।

(9) ई–निविदा पत्र बेवसाईट **www.eproc.bihar.gov.in** से प्राप्त किया जा सकता है। संवेदक द्वारा सिर्फ उपर्युक्त वेबसाईट से ही परिमाण विपत्र प्राप्त करने के उपरांत वेबसाईट पर ही इलेक्ट्रानिक निविदा पत्र को भरकर भेजना है। अन्य सभी महत्वपूर्ण कागजात/बैंक ड्राफ्ट/अग्रधन की राशि/सभी प्रमाण पत्र जो निविदा के लिए आवश्यक है को स्कैन कर ई–निविदा के साथ सलग्न करना अनिवार्य है।

(10) (क) Beltron Bid **Processing Fee** as appeared on the e-tendering website:- **www.eproc.bihar.gov.in** & **BOQ cost** as mentioned is mandatory to be paid through e-payment mode i.e. Internet payment gateway, (Credit/Debit card), Net Banking, NEFT/RTGS"

Bids along with necessary online payments must be submitted through e-procurement portal **www.eproc.bihar.gov.in** before the date and time specific in the NIT/Corrigendum. The department doesn't take any responsibility for the delay/Non submission of Tender/ Non Reconciliation of Online payment caused due to Non-availability of Internet Connection, Network Traffic/ Holidays or any other reason.

(ख) वांछित अग्रधन की राशि राष्ट्रीय बचत पत्र/किसान विकास पत्र/डाकघर सावधि जमा पासबुक/ 1, 2, 3 वर्षीय पोस्ट ऑफिस टाईम डिपोजिट जो बिहार राज्य से क्रय या जमा किया हो तथा प्रबंध निदेशक, BSEIDC Ltd., पटना के नाम प्रतिज्ञिप्त (Pledged) हो अथवा बिहार वित्त नियमावली के अनुसार प्रबंध निदेशक, BSEIDC Ltd. के नाम से प्रतिज्ञिप्त (Pledged) बिहार राज्य में स्थित *Nationlised/Scheduled* बैंक का फिक्सड डिपोजिट रिसिप्ट के रूप में प्रबंध निदेशक का कार्यालय, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड, पटना में दिनांक:– 15.01.2019 के 15:00 घंटे तक स्वयं/निबंधित डाक /स्पीड पोस्ट द्वारा निश्चित रुप से जमा किया जाना आवश्यक है अथवा EMD can also be paid through e-payment mode i.e. "Internet payment gateway, (Credit/Debit card), Net Banking, NEFT/RTGS". ऐसा नहीं करने पर निविदा मान्य नहीं होगा।

(11) निविदाकारों द्वारा इस्तेमाल किये जा रहे इन्टरनेट सर्विस में किसी प्रकार का व्यवधान उत्पन्न होने पर कोई भी दावा मान्य नहीं होगा। निविदाकारो को सलाह दी जाती है कि अपने निविदा को समय रहते उपर्युक्त वेबसाइट पर अपलोड कर लें। ताकि अंतिम समय में होनेवाले किसी प्रकार के व्यवधान से बच सकें।

(12) निविदाकार निविदा डालने से पहले अपने स्तर से भी प्रस्तावित कार्य स्थल पर भूमि उपलब्धता के संबंध में आश्वस्त हो लेगें।

(13) किसी भी प्रकार की जानकारी अथवा शुद्धि पत्र को वेबसाईट **www.eproc.bihar.gov.in** पर प्रकाशित किया जायेगा। बिना कारण बताये निविदा या उसके अंश को अस्वीकृत करने/रद्द करने का अधिकार सक्षम पदाधिकारी को सुरक्षित है।

(14) विशेष जानकारी हेतु अधोहस्ताक्षरी के कार्यालय में कार्य अवधि में सम्पर्क किया जा सकता है। ई–टेन्डरिंग की प्रकिया से संबंधित किसी भी प्रकार की जानकारी/सूचना हेतु सहायता कक्ष, ई–टेन्डरिंग कक्ष, प्रथम तल्ला, M/22, बैंक ऑफ इण्डिया भवन, रोड नं० 25, श्री कृष्णा नगर, पटना–800001, दूरभाष सं० 0612–2523006/9939035696.

13/12/18
मुख्य अभियंता
13-12-18

Chief Engineer
B.S.E.I.D.C. Ltd, Patna