

Schedule XLV - Form No. 61

Name of Work - Construction of
Upgraded⁽¹⁾ Secondary School
Buildings in Bihar.
Group No. - USS - 127 B.

BIHAR PUBLIC WORKS DEPARTMENT

Agency - [Form No. F-2] Manoj Kumar Singh.
ITEM RATE TENDER AND CONTRACT FOR WORKS

Agreement. _____ 85 F₂ of 2017-18.

General Rule and Direction for the guidance of Contractors.

1. All works proposed for execution by contract will be notified in a form of invitation to tender passed on a board hung up in the office of and signed by the Sub-divisional Officer/Executive Engineer.

This notice will state the work to be carried out the items and approximate quantities thereof as well as the date for submitting and opening tenders also; amount of earnest money to be deposited and the amount of the security deposit to be deposited by the successful tenderer and the percentage if any to be deducted from bills, copies of the specifications, designs and any other documents required in connection with this submission of tender signed for the purpose of identification by the Sub-divisional Officer/Executive Engineer shall also be open for inspection by the contractor at the office of the Sub-divisional Officer/Executive Engineer during office hours.

2. In the event of the tender being submitted by a firm, it must be signed separately by each member thereof or in the event of the absence of any partner, it must be signed on his behalf by a person holding a power-authorising him to do so.

3. Receipt for payments made on account of work when executed by a firm must also be signed by the several partners, except where the contractors are described in their tender as a firm in which case the receipt must be signed in the name of the firm by one of the partners, or by some other person having authority to give effectual receipt for the firm.

4. The memorandum of work tendered or and the memorandum of materials to be supplied by the Public Works Department and their issue rates shall be filled in and completed in the Office of the Sub-divisional Officer/Executive Engineer before the tender form is issued. If a form is issued to an intending tender without having been so filled in and completed, he shall request the office to have this done before he complete and delivers his tender.

| | |
|--|------------|
| 5. The amount of earnest money to be deposited will be :- | Rs. |
| If the amount of the estimate does not exceed Rs. 2,000 | 50 |
| If the amount of the estimate exceeds Rs. 2,000 but does not exceed Rs. 5,000 | 100 |
| If the amount of the estimate exceeds Rs. 5,000 but does not exceed Rs. 10,000 | 200 |
| For each additional Rs. 5,000 or portion of Rs. 5,000 additional earnest money | 100 |

6. Any Person who submits a tender shall fill up the usual printed form stating there at what rate he is willing to undertake each item of the work incomplete tender and tenders which propose any alteration in the work specified in the said form of invitation tenders, or which contain any other conditions of any sort, or omit to note the time within which the work can be finished, or which are not accompanied by the treasury challan for the required earnest money will be liable to rejection. No single tender shall include more than one work, but contractors who will to tender for two or more works shall submit a separate tender for each Tender shall bear the name of the work to which they refer written outside the envelope. Cash deposits for earnest money here in before mentioned shall be made in Government Treasuries and the challan thereof should be enclosed with the tender.

08.2013 & DSR

rates specified
specifications
which materials as

ed seventy
forty only.

and paise

28/6/17

28/6/17
Patna
106/17

7. The Engineer or his duly authorised assistant will open the tender in the presence of intending contractors who may be present at the time and will enter the amounts of the several tenders in comparative statements in a suitable form. In the event of a tender being rejected the challan for the earnest money forwarded therewith shall there upon be returned to the tenderer with a pay order for the amount of the earnest money.

8. The Engineer shall have the right of rejecting all or any of the tenders.

9. In the event of a tender being selected for acceptance the Engineer who opened the tender will, if he is competent to accept the tender, inform the tenderer or the selected tender who shall thereupon sign copies of the specification & other documents mentioned in rules 1 and 4 for the purpose of identification and for his acceptance with the tender. The tender of the selected tender shall also deposit the required amount of the security money within the prescribed time. If the tenderer fails to deposit the required amount of the security money within the prescribed time, the Engineer may reject the tender.

If the Engineer is not competent to accept the tender himself, he will inform the tenderer of the tender which he decides to recommend for acceptance. Such tenderer shall thereupon sign forth with copies of the specification and other documents mentioned in rules 1 and 4 and shall deposit the required amount of the security money within the prescribed time. The tender with the specification and other documents signed by the tenderer will then be forwarded for acceptance and the security money deposited shall be refunded to the tenderer.

10. When a tender is selected for acceptance the tender shall deposit the required amount of the security money in cash in the treasury and shall forward the challan to the Executive Engineer, Government. Securities may be endorsed to the Executive Engineer lieu of a cash deposit of the required amount of the security money. No tender shall be finally accepted until the required amount of the security money has been deposited.

11. The amount of security money to be deposited by the tenderer whose tender is selected for acceptance shall be 10% of the estimated value of the work & towards this amount the earnest money already deposited by him shall be credit. At least half of this security inclusive of the earnest money shall be deposited by the tenderer within such time as may be notified to him in writing by the officer opening tenders failing which the tender shall be liable to rejection.

Any balance of the security money outstanding after completion of the contract with the tenderer may be made up by deductions of 5% of the amount of each payment to be made to him under clause 12 of the conditions of contract for work done under the contract.

12. When a tender has been selected for acceptance & the required amount of the security money has been deposited the Engineer shall scrutinise all pages of the form of item rate tender & contract for works to see that the form has been properly filled up and signed by the contractor & the signature witnessed. He shall then if he is competent, to accept the tender, sign the acceptance of the tender, or, if he is not so competent shall send the form for signature of the acceptance of the officer competent to accept the tender.

Chief Engineer
S.E.P.D. Ltd. P. 10/11/12

M. A. J. D. 11/12

I/We hereby tender for the execution for the Governor of Bihar of the work specified in the under written memorandum at the rates specified therein within a period of years month from the date of written order to commence and in accordance in all respects with the specifications designs, drawing, and other documents referred to rule hereof and Subject to the annexed conditions of contract and with such materials as are provided for by and in other respects in accordance with, such conditions so far as applicable.

rates specified
specifications
such materials as

i) If several sub-work are included they should be retained in a separate list.

- [a] Name of work Construction of Upgraded Secondary
School Building in Bihar, Gr. No.-USS-1278
- [b] Estimated cost M-S. Moulkola, Pirpaiti, Bhagalpur
- [c] Earnest money
- [d] Initial security deposits (including earnest money) to be deposited before the commencement of the work
- [e] Percentage to be deducted from bills Rs. 5% (Rupees five percent)
- [f] Time required for the work from date of written order to commence
..... monthly
- [g] Date of written order to commence
- [h] Total number of item of work tendered for

rk-

| Item No. | Item of work | RATE TENDERED | | Per |
|----------|--------------|---------------|----------|-----|
| | | In figures | In words | |
| | | | | |

28/6/12
Chief Engineer
BSEIDCL Ltd Patna

dred seventy
ise forty only.

ven and praise

Chief Engineer

B. S. E. L. D. C. Ltd. Patna

ineer

Patna

Керемет

$$\frac{24}{28} \mid 6 \mid 17$$

[illegible]

28/6/17
gineer
Ltd, Patna
S. K. Singh
28/06/17

td.

11.08.2013 & DSR

at the rates specified
the specifications
with such materials as

e work-

hundred seventy
paise forty only.

seven and paise
y.

hundred seventy
d paise forty only.

ly seven and paise
only.

28/6/17
Engineer
C. Ltd, Patna
S. K. Choudhary
28/6/17

should this tender be accepted I/we hereby agree to abide by and fulfill terms and provisions of the said conditions of contract annexed hereto so applicable, or in ssors in office the sums of money mentioned in the said cond

Dated the _____ day of _____ 20____

*Signature, of contractor before comission of tender

with

Address

Occupation

Signature of witness to contractor's signature

The above tender is hereby accepted by me on behalf of the Governor of

Dated the _____ day of _____ 20____

signature of the
accepting the te

Acceptances communicated on.....

signature of the
taking the

CONDITIONS OF CONTRACT

Compensation

Clause 1:- All compensation or other sums of payable by the contract Government under the terms of his contract may be deducted from, paid sale of a sufficient part of his security deposit or from the Interest arising there or from any sums which may be due or may become due to the contractor Government on any account whatsoever and in the event of his security de being reduced by reason of any such deduction or sale as aforesaid, the contractor shall within ten days there after make good in cash or Government security endorsed as aforesaid any sum or sums which may have been deducted from arised by, as aforesaid his security deposit of any part thereof.

The work should not be considered untill such date as the Executive Engineer shall certify as the date on which the work is finished after necessary rectification of defects as pointed by the Executive Engineer or his authorised agents are fully contractor to the Engineer's satisfaction.

Clause 2 :- The time allowed for carrying out the work as entered in the shall be strictly observed by the contractor and shall be reckoned from the date which the written order to comence work is given to the contractor. The work throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the contract on the part of the contractor) and the contractor shall pay as compensation an amount equal to 1/2 percent on the amount of the estimated cost of the whole work as shown by the tender every day that the work remains uncommenced or unfinished after the proper And further to ensure good progress during the execution of the work the contractor shall be bound in all cases in which the time allowed for any work exceeds month to complete one fourth of the whole of the work before one - fourth whole time allowed under the contract has elapsed one-half of the work before half of such time elapsed and three-fourths of the work, before three fourths of time has elapsed in the event of the contractor failing to employ with this contract I shall be liable to pay as compensation an amount equal to 1/2 percent on the estimated cost of the whole work for every day that the due quantity of remains incomplete provided always that the entire amount of compensation paid under the provisions the clause shall not exceed 10 percent of the estimated cost of the work as shown in the tender.

Action when persnte security deposit foreited

Clause 3 :- In any case which under any clause or clauses of or this contract the contractor shall have rendered himself laible to pay compensation amount to the whole of his security deposit in the hands of Government (where paid in sum or deducted by instalments) the Executive Engineer on behalf on the Government shall have been powered to adopt any of the following courses, may deem best suited to the enterest of Government -

(a) To rescind the contract (of which rescind notice in writing to the contractor under the hand of the Executive Engineer shall be conclusive evidence) and which case the security deposit of the contractor shall be absolutely at the disposal of Government.

मनाच जयपुर

24/6
28/6

(b) To employ labour paid by the Public Works Department and to supply materials to carry out the work, or any part of the work, debiting the construction with most of the labour and the price of the materials (of the amount of which cost and certificate of the Engineer-in-charge shall be final and conclusive against the contractor), and crediting him with the value of the work done, in all respects in the same manner and at the same rates as if it had been carried out by the contractor under terms of his contract, the certificate of the Executive Engineer as to the value of the work done shall be final and conclusive against the contractor.

(c) To measure up the work of the contractor and to take such part of the work as the contractor as shall be unexecuted out of his hands, and to give it to another contractor to complete in which case any expenses which may be incurred in excess of the sum which would have been paid to the original contractor if the whole work had been executed by him (of the amount of which excess the certificate in writing of the Executive Engineer shall be final and conclusive) shall be born and paid by the original contractor and made be deducted from any money due to him by Government under the contract or otherwise, or from his security deposit or the proceeds of sale thereof, or a part thereof.

In the event of any of the above courses being adopted by the Executive Engineer, the contractor shall have no claim to compensation for any loss sustained by reason of his having purchased or procured any materials or entered into any agreement, or made advances on account of or with a view to execution of the work or performance of the contract. And in case the contract shall be rescinded under the provision aforesaid, contractor shall not be entitled to recover or be paid any sum for any work here-to-fore actually performed under this contract unless and until the Executive Engineer shall have certified in writing the performance of such work and the value thereof in respect thereof and he shall only be entitled to be paid the values so certified.

Clause 4 :- In any case in which any of the powers, conferred upon the Executive Engineer by clause 3 thereof shall have become exercisable and the same shall not be exercised the non-exercise thereof shall not constitute waiver of the conditions here and the power shall not with standing be exercisable in the event of any future case of default by the contractor for which by any clause or clauses hereof he is declared liable. Compensation amounting to the whole of his security deposit and the liability of the contractor for past and future compensation shall remain unaffected in the event of the Executive Engineer putting in force the powers vested in him under the preceding clause. He may, if so desires, take possession of all or any tools, plants, materials and equipment in or upon the works of the site thereof or belonging to the contractor or procured and intended to be for the execution of the work or any part thereof paying or owing for the same in the contract at the account rates, or in case of these not being available at current market rates to be certified by the Executive Engineer whose certificate thereof shall be final, otherwise the Executive Engineer may notice in writing the contractor or his clerk of the work, foreman or other authorised agent require him to remove such tools, plants, materials or stores from the premises (within a time to be specified in such notice) and in the event to the contractor failing to comply with any requisition the Executive Engineer may remove them at the contractor expense or sell them by auction or private sale on account of the contractor and at his risk in all respects, and the certificate of the Executive Engineer as to the expense of any such sale and the amount of the proceeds and expense of any such sale be final and conclusive against the contractor.

Clause 5 :- If the contractor shall desire any extension of the time for completion of the work on the ground of his having been unavoidably hindered in its execution or on any other ground other than those mentioned in clause 12 (a) he shall submit in writing to the Executive Engineer within 40 days from the date of starting of the work on account of which he desires such extension as aforesaid and the Executive Engineer shall, if in his opinion (which shall be final) reasonable grounds be shown for authorised such extension of time, if any, as may in his opinion be necessary. The Executive Engineer shall at the same time inform the contractor whether he is entitled to compensation for the delay.

contractor remains liable to pay compensation if action not taken under clause 2.

Power to take possession of or require removal of or sell contractor plant.

Extension of time

Ltd.

11.08.2013 & DSR

at the rates specified with the specifications with such materials as

the work-

nt

one hundred seventy and paise forty only.

Fifty seven and paise / only.

of Engineer
D.C. Ltd, Patna

28/06/17

S.S.E.I.D.C. Ltd, Patna

28/6

28/6/17

Final certificate

Clause 6:- On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (herein after called the Engineer-in-charge) of such completion, but no such certificate be given, nor shall the work be considered to be complete until the contractor no such certificate be given, nor shall the work be considered to be complete until the contractor shall have removed from the area of the premises (to be distinctly marked by the Executive Engineer in the site plan) on which the work shall be executed all scaffolding surplus materials, and rubbish, and cleaned of the dirt from all wood-work, doors, windows, walls, floors or other parts of any building, in upon or about which the work is to be executed, or of which he may have had possession for the purpose of the execution thereof, not until the work shall have been measured by the officer of the Public Work Department in accordance with rules of Department whose measurements shall be binding and conclusive against the contractor. If the contractor shall fail to comply with the requirements of this clause as to removal of scaffolding, surplus materials and rubbish and cleaning off dirt on or before the date fixed for completion the work the Engineer-in-charge may at the expense of the contractor remove such scaffolding, surplus materials and rubbish and dispose of the same as he thinks fit and clean of such dirt as aforesaid, and the contractor shall forth with pay amount of all expense so incurred, and shall have no claim in respect of any such scaffolding or surplus materials as aforesaid, except for any sum actually realised by the sale thereof.

Payment of in terms date
certificate to be regarded
as advance and Bill to be
submitted monthly.

Clause 7:- A bill shall be submitted by the contractor each month or before the date fixed by the Engineer-in-charge for all work executed in the previous months and the Engineer-in-charge or his subordinate shall take the requisite measurement for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible, before the expiry of the days from the presentation of the bill. If the contractor does not submit the bill within the time fixed as aforesaid, the Engineer in-charge or his subordinate shall measure up the said work in the presence of the contractor whose counter signature on the measurement list will be sufficient warrant, and the Engineer-in-charge or his subordinate shall prepare at bill from such list which shall be binding to the contractor in all respects.

Provided that, if any balance of the 10% security is outstanding from each such payment shall be deducted so much not exceeding 5% may be necessary to make up the balance of the security. All such intermediate payment to the contractor shall be regarded as payments by way of advance against the final payments only and not as payments for work actually done and completed and shall not preclude the reputing of bad, unsound and imperfect or unskilful work to be removed and taken away and reconstructed or recreated be considered as an admission of due performance of the contractor, or any part thereof in any respect, or the actual of any claim nor shall it conclude, determine or affect in any way the powers of the Engineer-in-charge under these conditions or any of them as so the final settlement or adjustment of the accounts or in any other way vary or affect the contract.

Stores supplied
Government

* Clause 8:- The final bill shall be prepared by the officer of the Public Work Department in accordance with the rules of the department in the presence of the contractor within the month of the date fixed for completion of the work.

Clause 9:- If the specification or estimate of the work provides for the use of any special description of material to be supplied from the Engineer in-charge's stores or if it is required that the contractor shall use certain stores to be provided by the Engineer-in-charge under the conditions of this contract or (such materials and stores, and the prices to be charged therefore as herein after mentioned being so far as practicable for the convenience of the contractor, but not so as in any way to control the meaning or effect of this contract are specified in schedule or memorandum here to annexed) the contractor shall be supplied with such materials and stores noted in the annexed such schedule required from time to time to be used by him for the purposes of the contract, only and the value of the full quantity of materials and stores so supplied at the rates specified in the said schedule may be set off or deducted from any sums then due or there after to become due to the contractor under the contract or otherwise, or against or form the security deposit, or the proceed of sale thereof, if the same is held in Government security the same or sufficient portion thereof in this case sold for the purpose. All materials supplied to the contractor shall remain the absolute property of Government and shall not on any accounts be removed from this site of the work and shall at all times be open to

240
28/6

by the Engineer-in-charge. Any such materials unused and in correctly in condition at the time of the completion or determination of the contract shall be to the Engineer-in-charge's store, at the prevailing market rate or at the issue ever is less if by a notice in writing under his hand he shall so require, but the shall not be entitled to return any such materials unless with such consent have no claim for compensation on account of any such materials so supplied aforesaid being unused by him, or for any wastage to or any such materials.

use 10 :- The contractor shall execute the whole and every part of the work in substantial and workman like manner, and both as regards materials and in every respect in strict accordance with the specifications. The contractor confirm exactly, fully and faithfully to designs, drawings, and instructions in relating to the work signed by the Engineer-in-charge and lodged in his office and the contractor shall be entitled to access at such office, for the purpose of during office hours, and the contractor shall, if he so require be entitled at his expenses to make or cause to be made copies of the specification, and of all such drawings and instructions as aforesaid.

use 11 :- Engineer-in-charge shall have power to make any alteration in additions original specifications, drawings and instructions that may appear to him to be necessary or advisable during the progress of the work. The contractor shall be bound to do the work in accordance with any instructions which may be given to him in writing by the Engineer-in-charge, and such alteration shall not invalidate the contract and any additional work which the contractor may be directed to do in the above specified as part of the work shall be carried out by the contractor on the same conditions in all respects on which he agreed to do the main work, and at the same rates as are specified in the tender of the main work. The time for completion of the work shall be extended in the proportion that the additional work bears to the original work and the certificate of the Engineer-in-charge shall be conclusive as to the proportion and to the additional work includes any class of work, for which no rates are specified in this contract then such class of work shall be carried out at the rates specified in the sanctioned schedule or rates of the locality during the period when the work is being carried on and if such last mentioned class of work is not entered in the schedule of rates of the district then the contractor shall within seven days of the date of receipt of the order to carry out the work inform the Engineer-in-charge of the class of work in his intention to charge for such class of work and if the Engineer-in-charge agrees to this rate he shall be noticed in writing be at liberty to cancel his order for such class of work and arrange to carry it out in such manner as he may think fit, provided always that if the contract shall commence work or in our expenditure in regard thereof before the rate shall have been determined as lastly mentioned then and in such case he shall only be entitled to be paid in respect of the work carried out or expenditure incurred by him prior to the date of the determination of the rates as aforesaid according to such rate or rates as shall be fixed by the Engineer-in-charge in the event of a dispute the decision of the superintending Engineer of the circle will be final.

provided always that the contractor shall not be entitled to any payment for any additional work done unless he has received an order in writing from the Engineer-in-charge for the additional work the contractor shall be bound to submit his claim for any additional work done during any month on or before the 15th days of the following month accompanied by a copy of the order in writing of the Engineer-in-charge for the additional work and that contractor shall not be entitled to any payment in respect of such additional work if he does not submit his claim within date aforesaid period.

Clause 12 :- If at any time after the commencement of the work the Government of India shall for any reason whatsoever not require the whole thereof as specified in the contract to be carried out, the Engineer-in-charge shall give notice in writing of the fact to the contractor who shall have no claim to any payment of compensation whatsoever on account of any profit or advantage, which he might have derived from the execution of the work in full, but which he did not derive in consequence of the full amount of the work not having been carried out neither shall he have any claim for compensation by reason of any alteration having been made in the original specification, drawings, designs and plans on which shall involve any installment of the work as originally contemplated.

12 (a) As contained in G O 1929 dated 11.9.56.

Work to be executed in accordance with specification drawing other etc.

Alteration in specifications and designation.

Do not in validate contract

Time in consequence of alteration

Rate for work no in estimate or schedule of rates of the district.

Compensation for alteration in or restriction of work to be carried out.

ation Ltd.

hool

ola

n dated : 11.08.2013 & DSR

randum at the rates specified
jects with the specifications
act and with such materials as

ent of the work-

S

ount

One hundred seventy
it and paise forty only.

Fifty seven and paise
ity only.

Chief Engineer
I.D.C. Ltd, Patna

Chief Engineer
I.D.C. Ltd, Patna

Clause 12 (a) The contractor shall not be entitled to claim any compensation for loss suffered by him on account of delay by or on behalf of Government in the supply of materials as stores which the Government may have undertaken to supply where such failure is due to :-

(i) natural calamities, (ii) act of enemies, (iii) transport and procurement difficulties or (iv) circumstances beyond the control of the state Government.

In case of such failure in delay in the supply of materials or stores on an application by the contractor within 30 days from the date of such failure or delay, such extension of time shall be granted to the contractor for completion of the work as shall appears to the Engineer to be reasonable in accordance with the circumstances of the case. The decision of the Executive Engineer as to the extension of time shall be accepted as finally by the contractor.

Action and compensation payable in case of work.

Clause 13 :- If it shall appear to the Engineer-in-charge or his subordinate in-charge of the work that any work has been executed with unsound, imperfect or unskilful workmanship or with materials of any inferior description, or by any materials or articles provided by him for the execution of the work are unsound or of a quality inferior to that contracted for at otherwise not in accordance with the contract, the contractor shall on demand in writing from the Engineer-in-charge specifying the inadvertently passed certified and paid for, forthwith rectify or remove and re-contract the work so specified in whole or in part as the case may remove the materials or articles so specified and provided other proper and suitable materials or articles at his own proper charge and cost, and in the event of failing to do so within period to be specified by the Engineer-in-charge in his demand aforesaid the contractor shall be liable to pay compensation at the rate of one percent, on the amount of the estimate for every day not exceeding ten days while his failure to do so shall continue and in the case of any such failure the Engineer-in-charge may certify or remove, and re-execute the work or remove and replace with others, the materials or articles complained of as the case may be, at the risk and expense in all respects of the contractor.

Work to be taken to inspection

Clause 14 :- All work under in course of execution or executed in presence of the contractor shall at the times be open to the inspection and supervision of the Engineer-in-charge and his subordinates and the contractor shall at all times during the usual working hours and at all other time at which reasonable notice of the intimation of the Engineer-in-charge or his subordinate to visit the works shall have been given to the contractor, either himself to be present to receive orders and instruction, or have a responsible agent duly credited in writing present for that purpose orders given to the contractor's agent shall be considered to have the same force as if they had been given to the contractor himself.

Contractor or responsible Agents to be present.

Clause 15 :- The contractor shall give not less than five days notice in writing to the Engineer-in-charge or his subordinate-in-charge of the work before covering up or otherwise placing beyond the reach of measurement of any work in order that the same may be measured and correct dimensions thereof be taken before the same is so covered up or placed beyond the reach of measurement and shall not cover up or place beyond the reach of measurement of any work without the consent in writing of the Engineer-in-charge or his subordinate in-charge of the work shall be covered up or placed beyond the reach of measurement without such notice having been given or consent obtained, the same shall be uncovered at the contractor's expenses or in default thereof on payment or allowance shall made for such work on materials with which the same was effected.

Notice to be taken before work covered up

Clause 16:- If the contractor or his work-people, or servants shall break, deface, injure or destroy any part of a building in which they may be working or any building, road, road curves, fence enclosure water pipes, cables, drains, electric or telephone posts or wires, trees, grass or grassland or cultivated ground contiguous to the work or any part of it is being executed or if any damage shall happen to the work, while in progress from any cause whatsoever or any imperfection shall become apparent in if within three months (six months in the case of a road-work) after a certificate final of other of its completion shall have been given by the Engineer-in-charge

7912 Jm 115

Chief Engineer
B.S.E. & P.D. Dept.
28/6

Contractor liable for
damage done and for
imperfection a months
and after certificate

the rates specified
the specifications
such materials as

Contractor to supply to
plantladder scaffolding
etc

And is liable for damage arising for non-provision of light fencing etc.

Work not to be subject

Clause 19:- The Contractor shall not be assigned or subject without the written approval of the Executive Engineer. And if the contractor shall assign or subject his contract, or attempt so to do, or become insolvent proceedings to make any composition with his creditors or attempt so to do, or if any bribe, gratuity, gift loan, requisite, reward or advantage pecuniary of otherwise, shall either directly or indirectly be given promised, offered by the contractor, or any of his servant or agents to any public officer or person in the employ of Government in any way relating to his officer or employment or if any public officer or person shall become in any way directly or indirectly interested in the contract the Executive Engineer may there upon by notice in writing rescind the contract. The security deposit of the contractor shall there upon stand forfeited and be absolutely at the disposal of Government and the same consequence shall ensue as if the contract had been rescinded under clause 3 here of, in addition the contractor shall not be entitled to recover or be paid to any work therefore actually performed the under the contract.

Contract may
and security
be forfeited for sub
or if contract
insolvent

28/11
Chief Engineer
Bihar State Roadways Ltd, Patna
D.D.

Contract may be resinded
and security deposit for-
feited for subletting bribes
or if contractor become
insolvent

hundred seventy
thirty four only.

even and praise

67/28/6/17
Engineer
Ltd, Patna
Shekhar Singh
28/06/17

such payable by way of compensation to be considered reasonable compensation without reference to actual loss

Clause 20:- All sums payable by way of compensation under any of the conditions shall be considered as reasonable compensation to be applied to the use of the Government without reference to the actual loss or damages sustained and there not any damage shall have been sustained.

Clause 21 :- In the case of a sender by partners, any change in the constitution of the firm shall be forthwith notified by the contractor to the Engineer-in-charge or the information.

Charges in constitution of firm.

In case of failure to notify the change in the constitution within fifteen days the Engineer-in-charge may be notice in writing rescind the contract and the security deposit of the contractor shall thereupon stand forfeited and be absolutely at the disposal of the Government and the same consequences shall ensue as if the contract has been rescinded under clause 3 hereof, and in addition the contractor shall not be entitled to recover or be paid for any work therefore actually performed under the contractor.

Works to be under direction of Suprintending Engineer

Clause 22 :- All work to be executed under the contract shall be executed under the direction and subject to the approval in all respect of the superintending Engineer of the circle for the time being who shall be entitled to direct at what point or points and in what manner they are to be commenced, and from time to time carried on.

Clause 23 :- In case any dispute or difference shall arise between the parties or either of them upon any question relating to the meaning of the specifications, designs, drawings and instructions here before mentioned or as to the quality of workmanship or materials used on the work or as to the construction of any of the conditions or any clause or thing there in contained or as to any question, claim, rights of the parties, or any matter, or things whatsoever in any way arising out of or relating to the contract designs, drawings specifications, estimates, instruction order of these conditions or otherwise concerning the work or the execution, or failure to execute the same whether arising during the progress of the work or alter the completion or abandonment thereof or as the breach of those contract then either party shall forthwith give to the order notice of such dispute or difference and such dispute or difference shall be referred to the Superintending Engineer of the circle and his decision there on shall be final, conclusive and binding on all the parties.

Lum sum in estimate

(a) Clause 24 :- When the estimate on which a tender is made includes lump sum in respect of the contract shall be entitled to payment in respect of the items of work involved of the work in question the same rates as are payable under this contract such terms, for if the part of the work in question is not in the opinion of the Engineer-in-charge, capable of measurement the Engineer-in-charge, may at his direction pay the lump sum amounts entered in the estimate, and the certificate in writing of the Engineer-in-charge shall be final and conclusive against the contractor with regard to any sum payable to him under the provision of this clause.

Action where no specification.

Clause 25:- In the case of any class of work for which there is no such specification as is mentioned in rule 1, such work shall be carried out in accordance with the circle specification and in the event of there being no circle specification, then in such case the work shall be carried out in all respects in accordance with the instructions and requirements of the Engineer-in-charge.

Definition of works

Clause 26 :- The expression "work" or "works" where used in these conditions shall unless there be something either in the subject or context repugnant to such construction be construed and taken to mean the work by or virtue of the contract contracted to be executed whether temporary or permanent, and whether original, altered, substituted or additional.

Clause 27:- The terms and conditions of the agreement have been read/explained to me and.....certify.....clearly understand them

Witness.

Contractor

Bihar State Educational Infrastructure Development Corporation Ltd.

B.O.Q. FOR UPGRADED SECONDARY SCHOOLS IN BIHAR

Group No. : USS-127B

| S.N. | District | Block | Name of School |
|------|-----------|----------|----------------|
| 1 | BHAGALPUR | Pirpaiti | M.S. Maultola |

THE ITEM RATES ARE BASED ON BIHAR SCHEDULE OF RATES, BCD, effective from dated : 11.08.2013 & DSR 2013

TENDER FOR WORKS

I/we hereby tender for the execution for the Governor of Bihar of the work specified in the under written memorandum at the rates specified therein within a period of years month from the date of written order to commence and in accordance in all respects with the specifications designs, drawing, and other documents referred to rule hereof and Subjects to the annexed condition of contract and with such materials as are provided for by and in other respects in accordance with, such conditions so far as applicable.

MEMORANDUM

| | |
|---|---|
| (a) If several sub- | (A) Name of Work :- CONSTRUCTION OF UPGRADED SCHOOLS IN BIHAR |
| | (B) Estimated Cost :- Rs. 52,39,859=00 Agreement value :- Rs. 49,25,467=00 |
| (b) This deposit will be 5% of the estimated cost of the work. | (C) Earnest Money :- |
| (c) This percentage deduction from bills will be credited to the contractors security | (D) Initial security deposits (including earnest money) to be deposited before the Commencement of the work- Earnest Money :- Rs. 2,47,000- (Details attached) |
| | (E) Percentage to be deducted from bill Rs. 5% (Rupees five percent) |
| | (F) Time required for the work from date of written order to commence TWELVE MONTHS |
| | (G) Date of written order to commence :- |
| | (H) Total number of item of work tendered for :- 74 |

BUILDING WORKS : (Quantity per School)

CIVIL WORKS

| S.N | Sub | SOR | DESCRIPTION | Quantity | Unit | Rate | Amount |
|-----|-----|-------|---|----------|------|--------|---|
| 1 | | | 2.0 Earth Work | | | | |
| | | 2.8 | EARTH WORK IN EXCAVATION over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including dressing of sides and ramming of bottom, lift upto 1.5m including getting out the excavated soil and disposal of surplus soil as directed, within a lead of 50m. | | | | |
| | | 2.8.1 | ALL KINDS OF SOIL | 24.06 | CU.M | 178.40 | Rs. One hundred seventy eight and paise forty only. |
| 2 | | 2.26 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth: consolidating each deposited layer by ramming and watering lead of 50 m. | 0.00 | CU.M | 57.80 | Rs. Fifty seven and paise eighty only. |

2977 Jm Arz

5/3/28/6/11
Chief Engineer
B.S.E.I.D.C. Ltd, Patna
246
28/6/11

| | | | |
|---|--|----------------|---|
| 3 | | 2.28 | SUPPLY & Foundation under floor ramming, dressing and |
| 4 | | 2.29.1 | SURFACE ground vegetation exceeding disposal of m and lift up |
| 5 | | | 4.0 Concrete |
| | | 4.5 | Providing and |
| | | 4.5.6 | 1:3:6 (1 Cement : 3 graded stone nominal size) |
| 6 | | | 5.0 Reinforced Concrete |
| | | 5.1 | Providing position, of reinforced excluding the and shuttering reinforcement plinth level. |
| | | 5.1.2 | 1:1½:3 (1 Cement sand : 3 graded 20 mm nominal FOUNDATION. |
| 7 | | 5.2 | Reinforced concrete work in wall including attachment butteresses, plinths, courses, fillets, piers, abutments struts, etc. upto excluding costs shuttering, finishing reinforcement. |
| | | | Col. in plinth & s |
| | | 5.2.2 | 1:1½:3 (1 Cement sand : 3 graded stone 20 mm nominal size) |
| 8 | | 5.3+ 5.44.4 | Reinforced concrete work in beams , excluding cost shuttering and reinforcement 1:1½:3 (1 cement: 1½ : 3 graded stone aggregate nominal size) |

2017 Jan 14

| | | | | | | |
|---|----------------|--|--------|----------|---------|--|
| 3 | 2.28 | SUPPLY AND FILLING in plinth & Foundation with local sand and under floors including watering, ramming, consolidating and dressing and dressing complete. | 173.23 | CU.M | 186.30 | Rs. One hundred eighty six and paise thirty only. |
| 4 | 2.29.1 | SURFACE DRESSING of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m | 3.50 | 100 SQ.M | 642.50 | Rs. Six hundred forty two and paise fifty only. |
| 5 | 4.5 | 4.0 Concrete Work Providing and laying of in position | 19.18 | CU.M | 2554.60 | Rs. Two thousand five hundred fifty four and paise sixty only. |
| | 4.5.6 | 1:3:6 (1 Cement : 3 Coarse sand : 6 graded stone aggregate 40mm nominal size) | | | | |
| 6 | | 5.0 Reinforced Cement Concrete | 33.68 | CU.M | 3851.00 | Rs. Three thousand eight hundred fifty one only. |
| | 5.1 | Providing and laying of in position, of specified mix of reinforced cement concrete, excluding the cost of centering and shuttering, finishing and reinforcement - all work upto plinth level. | | | | |
| | 5.1.2 | 1:1½:3 (1 Cement : 1½ Coarse sand : 3 graded stone aggregate 20 mm nominal size) IN FOUNDATION. | | | | |
| 7 | 5.2 | Reinforced cement concrete work in wall (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor v level, excluding costs of centering, shuttering, finishing and reinforcement. | 24.83 | CU.M | 3903.40 | Rs. Three thousand nine hundred three and paise forty only. |
| | | Col. In plinth & superstructure | | | | |
| | 5.2.2 | 1:1½:3 (1 Cement : 1½ Coarse sand : 3 graded stone aggregate 20 mm nominal size). | | | | |
| 8 | 5.3+ 5.44.4 | Reinforced cement concrete work in beams, upto five level excluding cost of centring, shuttering and finishing and reinforcement with 1:1½:3 (1 cement: 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) | 7.04 | CU.M | 4161.12 | Rs. Four thousand one hundred sixty one and paise twelve only. |

2017 Jan 14

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

24/1

28/6

28/6/17
28/6/17

| | | | | |
|----|------|----------------|--|--|
| 9 | | 5.3+ 5.44.4 | Rein- work level shut rein 1:1 :3 g nim | |
| 10 | | 5.3+ 5.44.4 | Re wo ro co fin 1: :3 ni | |
| 11 | | 5.3+ 5.44.4 | R W 10 8 11 | |
| 12 | | 5.14 | | |
| | 12.1 | 5.14.1 | | |
| | 12.2 | 5.14.6 | | |
| | 12.3 | 5.14.3 | | |
| | 12.4 | 5.14. | | |
| | 12.5 | 5.14. | | |
| 13 | | 5. | | |
| | 13.1 | 5.29 | | |
| | 13.2 | 5.29 | | |
| | 13.3 | 5.29 | | |
| | 13.4 | 5.29 | | |
| | 13.5 | 5.2 | | |
| | 13.6 | 5.2 | | |

| | | | | | | |
|----|----------------|--|---------|-------|---------|--|
| 9 | 5.3+ 5.44.4 | Reinforced cement concrete work in LINTEL BAND upto five level excluding cost of centring, shuttering and finishing and reinforcement with 1:1½:3(1cement: 1½ coarse sand :3 graded stone aggregate 20 mm nominal size) | 32.48 | CU.M | 4161.12 | Rs. Four thousand one hundred sixty one and paise twelve only. |
| 10 | 5.3+ 5.44.4 | Reinforced cement concrete work in suspended floors & roofs upto five level excluding cost of centring, shuttering and finishing and reinforcement with 1:1½:3(1cement: 1½ coarse sand :3 graded stone aggregate 20 mm nominal size) | 63.27 | CU.M | 4161.12 | Rs. Four thousand one hundred sixty one and paise twelve only. |
| 11 | 5.3+ 5.44.4 | Reinforced cement concrete work in STAIRCASE upto five level excluding cost of centring, shuttering and finishing and reinforcement with 1:1½:3(1cement: 1½ coarse sand :3 graded stone aggregate 20 mm nominal size) | 8.06 | CU.M | 4161.12 | Rs. Four thousand one hundred sixty one and paise twelve only. |
| 12 | 5.14 | Centering and shuttering including strutting, propping etc. and removal of form for - | 0.00 | SQ.M. | 137.78 | Rs. One hundred thirty seven and paise seventy eight only. |
| | 12.1 | Foundations, footings, bases of columns etc. for mass concrete. | | | | |
| | 12.2 | Columns | | | | |
| | 12.3 | ROOF SLAB | | | | |
| | 12.4 | Lintels, beams, plinth beams,- | | | | |
| | 12.5 | Stairs (excluding landings). | | | | |
| 13 | 5.29 | Reinforcement for RCC work including straightening, cutting bending, placing in position and binding all complete. | 1584.30 | kg | 63.40 | Rs. Sixty three and paise forty only. |
| | 13.1 | Mild steel 6.00 mm dia | | | | |
| | 13.2 | Thermo- Mechanically Treated bars TMTC-500- 8mm dia. | | | | |
| | 13.3 | Thermo- Mechanically Treated bars TMTC-500- 10mm dia. | | | | |
| | 13.4 | Thermo- Mechanically Treated bars TMTC-500- 12mm dia. | | | | |
| | 13.5 | Thermo- Mechanically Treated bars TMTC-500- 16mm dia. | | | | |
| | 13.6 | Thermo- Mechanically Treated bars TMTC-500- 20mm dia. | | | | |
| | | | | | | |

Chief Engineer
S.E.I.D.C. Ltd. P.O. Secy
28/06/11

| | | | | | | | |
|----|------|----------------|---|---------|-------|---------|---|
| 14 | | | 6.0 Brick Work (A) | | | | |
| | 14.1 | 6.1 A | Brick work with bricks of class of class designation 100 A in foundations and plinth in : | | | | |
| | | 6.1.14A | Cement mortar 1: 6 (1 cement : 6 coarse sand) | 25.29 | CU.M | 3713.5 | Rs. Three thousand seven hundred thirteen and paise fifty only. |
| | 14.2 | 6.1.12/1 | Cement mortar 1: 4 (1 cement : 4 coarse sand) | 7.03 | CU.M | 3914.60 | Rs. Three thousand nine hundred fourteen and paise sixty only. |
| 15 | 15.1 | 6.1 A | Brick work with bricks of class of class designation 100 A in superstructure upto floor V level in : | | | | |
| | | 6.1.14 A+6.3A | Cement mortar 1: 6 (1 cement : 6 coarse sand) | 173.48 | CU. M | 4092.30 | Rs. Four thousand ninety two and paise thirty only. |
| | 15.2 | 6.18.4A +6.19A | Cement mortar 1: 4 (1 cement : 4 coarse sand) | 15.28 | SQ.M. | 500.10 | Rs. Five hundred and paise ten only. |
| 16 | | | 9.0 Wood Work | | | | |
| | | 9.82.1 | Providing and fixing M.S. grills of requirement pattern in frames of windows etc. with M.S. flats square or round bars etc. all complete | 1432.00 | Kg | 83.90 | Rs. Eighty three and paise ninety only. |
| 17 | | | 10.0 Steel Work | | | | |
| | | 10.5 | Providing and fixing in position collapsable steel shutters with vertical channels 20X10X2 mm and braced with flat iron ds 20X5 mm size with top and bottom rail of T-iron 40X40X6 mm with 40 mm dia steel pulleys completes with bolts-nuts locking arrangement stoppers handles including applying a priming coat of approved steel primer. | 9.75 | SQ.M | 3634.00 | Rs. Three thousand six hundred thirty four only. |
| 18 | | 10.7 | Providing and fixing 1 mm thick M.S. sheet door & window with frame of 40X40X6 mm angle iron and 3 mm gusset plates at the junction and corners all necessary fittings complete including applying a priming coat of approved steel primer. | 49.44 | SQ.M. | 2247.80 | Rs. Two thousand two hundred forty seven and paise eighty only. |

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

240.
28/628/6/12
28/06/12

28/6/12

| | | | | | | |
|----|---------|---|--------|-------|---------|---|
| 19 | 10.12 | Providing and fixing steel glazed doors, windows and ventilators of standard rolled steel sections, joints mitred and welded with 15x3 mm lugs 10 cm long with steel lugs embedded in cement concrete blocks 15x10x10 Cm of 1:3:6 (1 Cement:3 coarse sand : 6 graded stone aggregate 22 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of glass panes with glazing clips and special metal-sash putty of approved make complete including applying a priming coat of approved steel primer; excluding the cost of metal beading and other fitting except necessary hinges or pivots as required. | 66.54 | SQ.M. | 2924.00 | Rs. Two thousand nine hundred twenty four only. |
| 20 | 10.19 | Providing and fixing M.S. Fan clamp type 1 of 16 mm | 22.00 | EACH | 108.20 | Rs. One hundred eight and paise twenty only. |
| 21 | 10.32.2 | Steel work welded in built up sections as per drawing including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using steel in Stairs / Balcony railing. | 540.00 | K.G. | 77.10 | Rs. Seventy seven and paise ten only. |
| 22 | 10.33 | Providing and fixing hand rail by welding etc. to steel ladder railings & staircases railing including applying a priming coat of approved steel primer | | | | |
| | 10.33.1 | MS tube (medium) 40 mm nominal bore | 108.00 | K.G. | 81.60 | Rs. Eighty one and paise sixty only. |
| | | 11.0 Flooring | | | | |
| 23 | 11.8 | 52 mm thick cement concrete flooring with metallic concrete hardener topping under layer 40 mm thick cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 20 mm nominal Size) and top layer 12 mm thick metallic cement hardener consisting of mix 1:2 (1 cement hardener : 2 stone aggregate 6 mm nominal size) by volume hardening compound is mixed @ 2 litre per 50 kag of cement or as per manufacture specification. This includes cost of cement slurry, etc, but excluding the cost of nosing of steps etc. complete. | 663.85 | SQ.M | 316.10 | Rs. Three hundred sixteen and paise ten only. |

28/6/17
Chief Engineer

B.S.E.I.D.C. Ltd Patna

24/6

28/6

28/06/17

| | | | | | | |
|----|---------------|--|---------|-------|--------|--|
| 24 | 11.14 | Extra for making chequers of approved pattern on cement concrete floors, steps, landing, pavements etc. | 228.28 | SQ.M | 16.60 | Rs. Sixteen and paise sixty only. |
| 25 | 11.72 | Providing designation 100 - A, BRICK FLAT SOLING joints filled with local sand including cost of watering, taxes and royalty all complete as per building specification and direction of Engineer Incharge. | 278.11 | SQ.M | 212.90 | Rs. Two hundred twelve and paise ninety only. |
| 26 | 11.76 | Providing average 150 mm thick dry remmed Khoa beaten to 112 mm (Compacted with water) made of well burnt or Jhama bricks including ramming properly till compacted thickness is achieved. Curing and carriage of water with all leads, making proper slope and blinding the top with cement mortar, (1: 10) all complete as per building specification and direction of E/1 | 214.55 | SQ.M | 283.50 | Rs. Two hundred eighty three and paise fifty only. |
| 27 | | 12.0 Roofing | | | | |
| | 12.78 | Providing & fixing on wall face unplasticised - Rigid P.V.C. rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS: 5382 leaving 10mm gap for thermal expansion. Single socket ed pipes. 110 mm dia | | | | |
| | 12.78.2 | 110 MM RAIN WATER PIPE | 82.31 | Metre | 199.60 | Rs. One hundred ninety nine and paise sixty only. |
| 28 | 12.79.5.2 | BEND | | | | |
| | | 110 MM | 10.00 | EACH | 153.40 | Rs. One hundred fifty three and paise forty only. |
| 29 | 12.79.6.2 | SHOE - 110MM | 10.00 | EACH | 293.35 | Rs. Two hundred ninety three and paise thrity five only. |
| 30 | | 13.0 Finishing | | | | |
| | 30.1 | 13.11.2 Cement Plaster in coarse sand with 12 mm cement plaster 1:4 (1 Cement : 6 Coarse Sand) | 229.60 | SQ.M. | 90.70 | Rs. Ninety and paise seventy only. |
| | 30.2 | 13.11.4 Cement Plaster in coarse sand with 12 mm cement plaster 1:6 (1 Cement : 4 Coarse Sand) | 1290.96 | SQ.M. | 79.10 | Rs. Seventy nine and paise ten only. |
| 31 | 13.13.13.13.2 | 20 mm thick plaster of mix : 1 : 4 (1 Cement ; 4 Coarse Sand) | 41.62 | SQ.M | 128.10 | Rs. One hundred twenty eight and paise ten only. |
| | 13.13.4 | 20 mm thick plaster of mix : 1 : 6 (1 Cement : 6 Coarse Sand) | 663.16 | SQ.M. | 110.00 | Rs. One hundred ten only. |

B.S.E.I.D.C. Ltd, Patna

24/6
28/6
28/6/17

| | | | | | | | |
|-----------------------|--------|---------|--|---------|-------|--------|--|
| 33 | | 13.17 | 12 mm cement Plaster 1:3 (1 Cement : 3 Coarse Sand) finished with a floating coat of neat Cement | 48.53 | SQ.M. | 127.00 | Rs. One hundred twenty seven only. |
| 34 | | 13.24.2 | 6 mm Cement Plaster to Ceiling of mix - | | | | |
| | | | cement plaster 1:4 (1 Cement : 4 Coarse Sand) | 448.06 | SQ.M. | 68.20 | Rs. Sixty eight and paise twenty only. |
| 35 | | 13.26 | Neat Cement Punning | 315.08 | SQ.M | 25.90 | Rs. Twenty five and paise ninety only. |
| 36 | | 13.70. | White washing with lime to give an even shade | | | | |
| | | 13.70.1 | New work (three or more coats) | 1562.77 | SQ.M | 9.00 | Rs. Nine only. |
| 37 | | 13.78 | Applying one coat of cement primer of approved brand and manufacturer on wall surface. | | | | |
| | | 13.78.1 | cement primer on outer wall surface | 730.25 | SQ.M | 22.10 | Rs. Twenty two and paise ten only. |
| 38 | | 13.79 | Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade | | | | |
| | | 13.79.1 | New work (three or more coats) | 730.25 | SQ.M | 51.70 | Rs. Fifty one and pasie seventy only. |
| 39 | | 13.93 | Painting with Synthetic enamel paints of approved brand and manufacture of required color to give an even shade. | | | | |
| | | 13.93.1 | Two or more coats on new work | | | | |
| | | | Paiting over Steel surface | 283.92 | SQ.M | 42.00 | Rs. Forty two only. |
| 23.0 Pile Work | | | | | | | |
| 40.1 | 23.2.5 | | Making 25 cm (10") dia bore up to 4 Mtr Depth below ground with hand auger of approved quality in ordinary soil (Vide classification of soil item A) true to plumb and without eccentri city in any stage of operation and disposal of gthe excavated earth up to 50 mtr. lead in eluding all lifts. all complete as per approved design and directions of E/I | 346.50 | Metre | 80.40 | Rs. Eighty and paise forty only. |

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

24/6

28/6

28/6/12

गणेश राम सिंह

| | | | | | | | |
|----|------|--------------|---|--------|------|---------|---|
| | 40.2 | 23.2.6 | 63 cm (25) UNDER REAM making 63 cm (25) dia under ream at required with hand auger of approved quality in ordinary soil (Vide classification of soil item-A) true to plumb and without iccentric city in may stage of operation and disposal of the excavated earth up to 50 mts. lead in eluding all lifts. All complete as per approved design and direction of (E/I) | 172.00 | Each | 85.70 | Rs. Eighty five and paise seventy only. |
| 41 | | | Sanitary Works | | | | |
| | | D.S.R 17.1.1 | Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S tap, 10 litre low white P.V.C. Flushing cistern with munally controlled device (handle level) conforming to IS:7231 Parryware/ Hindware with all fittings and fixtures complete including cutting and making good the walls and floors wherever required. | | | | |
| | | | White Vitreous China Orissa pattern W C pan of size 580 X 440 mm with integral type foot rest. | 8.00 | Each | 3265.25 | Rs. Three thousand two hundred sixty five and paise twenty five only. |
| 42 | | DSR 18.49.1 | Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 | | | | |
| | | | 15 mm nominal bore. | 8.00 | Each | 458.40 | Rs. Four hundred fifty eight and paise forty only. |
| 43 | | DSR 17.7.1 | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : | | | | |
| | | | White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps. | 4.00 | EACH | 2174.65 | Rs. Two thousand one hundred seventy four and paise sixty five only. |
| 44 | 44.1 | DSR 17.28 | Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. | | | | |
| | | 17.28.2 | Flexible pipe | | | | |
| | | 17.28.2.1 | 32 mm dia | 4.00 | EACH | 72.55 | Rs. Seventy two and pasie fifty five only. |
| | 44.2 | 17.28.2.2 | 40 mm dia | 1.00 | EACH | 74.90 | Rs. Seventy four and paise ninety only. |

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

24.6.
28/6

28/6/17

| | | | | | | | |
|----|------|--------------|--|-------|------|---------|---|
| 45 | | DSR 17.11 | Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug 40mm C.P brass waste and including painting of fittings and brackets, cutting and making good the wall wherever required : | | | | |
| | | 17.11.2 | Size 600x450x200mm | 1.00 | EACH | 2992.45 | Rs. Two thousand nine hundred ninety two and paise forty five only. |
| 46 | | DSR 18.52 | Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make | | | | |
| | | 18.52.1 | 15 mm nominal bore. | 5.00 | EACH | 618.70 | Rs. Six hundred eighteen and paise seventy only. |
| 47 | | 2.38A.2 | Providing & fixing stainless steel jali (grating) with or without hole for waste pipe for floor / nahani trap. | | | | |
| | | | 100 mm dia. Weight not less than 100 gms. | 2.00 | EACH | 23.37 | Rs. Twenty three and paise thirty seven only. |
| 48 | | 12.78 BSR | Providing and fixing on wall face unplasticised PVC (working pressure 4 kgf per sqm) rain water pipes conforming to IS : 4985 including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. | 76.21 | MTS | 199.60 | Rs. One hundred ninety nine and paise sixty only. |
| | | 12.78.2 | 110 mm diameter | | | | |
| 49 | | 12.79 | Providing and fixing PVC pipe fittings with all accessories | | | | |
| | 49.1 | 12.79.5.2 | 1) 110mm Plain bend PVC | 16.00 | Each | 153.40 | Rs. One hundred fifty three and paise forty only. |
| | 49.2 | 12.79.3.2 | 3) 110mm door tee PVC | 12.00 | EACH | 294.60 | Rs. Two hundred ninety four and paise sixty only. |

महोदय जयपुर

28/6/12
Chief Engineer
B.S.E.I.D.C. Ltd, Patna
28/6/12

| | | | | | | | |
|----|------|-------------------|--|-------|------|----------|--|
| 50 | | 19.30.1. 1/DSR | Constructing brick masonry chamber for Underground C.I. Inspection Chamber and bend with 75 class designation bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. Cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg. (weight of cover 23 kg. and weight of frame 15 kg) RCC top slab with 1:1.5:3 mix (1 cement:1.5 coarse sand :3 graded stone aggregate 20 mm mm nominal size) foundation concrete 1:5:10 mix (1 cement:5 coarse sand :10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm th. with cement mortar 1:3 (1 cement :3 coarse sand) finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design | | | | |
| | | | inside dimensions 455x610mm and 45 mm deep for single pipe with F.P.S. bricks | 6.00 | EACH | 4505.00 | Rs. Four thousand five hundred five only. |
| 51 | | 18.8/ DSR | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This includes joining of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of E/I | | | | |
| | | | Concealed work including cutting chases and making good the wall etc. | | | | |
| | 51.1 | a) 18.8.1 | 15mm dia | 35.00 | MTS | 254.95 | Rs. Two hundred fifty four and paise ninety five only. |
| | 51.2 | c) 18.9.5 | Exposed on wall 40mm dia | 75.00 | MTS | 343.55 | Rs. Three hundred forty three and paise fifty five only. |
| 52 | 52.3 | MR | Labour cost for preparation of BIHAR MAP on wall including painting all complete. | 1.00 | Each | 15150.00 | Rs. Fifteen thousand one hundred fifty only. |

महान्त जय अरु

Chief Engineer
B.S.E.I.D.C. Ltd, Patna
248
28/6.
28/06/17

| | | | | | | |
|------|------------|---|---------|------|---------|--|
| 53 | 18.48/ DSR | Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank | 1000.00 | LTS | 6.30 | Rs. Six and paise thirty only. |
| | | Providing and fixing of Borewell, Handpump with Submersible pump all complete. | | | | |
| | | Construction of 125 mm x 40mm dia x 75.00 mtr. Deep I.M III hand Tube Well | 1.00 | Each | 8635.50 | Rs. Eight thousand six hundred thirty five and paise fifty only. |
| 54.1 | | Part 'A' Cost of Materials India mark III hand pump with 8 nos. Connection Rod and one cylinder (With provision of force and uplift) | | | | |
| 54.2 | | 65 mm dia G.I. pipe medium quality (3mtrs length each). | 8.00 | Each | 1072.62 | Rs. One thousand seventy two and paise sixty two only. |
| 54.3 | | 125 mm dia UPVC casing pipe conforming to ISS | 27.00 | mtr | 318.15 | Rs. Three hundred eighteen and paise fifteen only. |
| 54.4 | | 40 mm dia length quantity G.I pipe conforming to ISS | 44.00 | mtr | 187.86 | Rs. One hundred eighty seven and paise eighty six only. |
| 54.5 | | 40 mm dia x 2 long PVC RIBEED strainer of approved quality | 2.00 | nos. | 183.82 | Rs. One hundred eighty three and paise eighty two only. |
| 54.6 | | 125 mm x 40 mm UPVC reducing socket (Heavy quality) | 1 | Each | 166.65 | Rs. One hundred sixty six and paise sixty five only. |
| | | Part - 'B' Labour Cost (Classification of soil item 'A') | | | | |
| | | Boring by jet dheki by suitable cutter of reduce as the case may be lowering 125 mm x U.P.V.C x 40 mm dia G.I pipe & strainer of standard quality iron, shoe, plug & socket etc. all complete including providing all tools and plants required for the job as per specification and direction of the engineer in charge. | 27 | mtr | 210.86 | Rs. Two hundred ten and paise eighty six only. |
| | | (i) 0 to 30.5 m | | | | |
| 54.7 | | (a) For 125 mm dia U.P.V.C pipe | | | | |
| 54.8 | | (b) for 40 mm dia G.I pipe | 3.5 | mtr | 105.46 | Rs. One hundred five and paise forty six only. |
| | | (ii) 30.5 m to 61.0 m | 30.5 | mtr | 121.28 | Rs. One hundred twenty one and paise twenty eight only. |
| 54.9 | | (a) For 40 mm dia G.I Pipe | | | | |
| | | (iii) 61.00 m to 75.00 m | 14 | mtr | 131.84 | Rs. One hundred thirty one and paise eighty four only. |

Chief Engineer

B.S. Choudhary, Patna

28/6/17

28/6/17

54

| | | | | | | |
|-------|--|---|----|------|---------|---|
| 54.10 | | a) For 40mm dia G.I pipe | | | | |
| 54.11 | | Providing all labour & tools and fitting & fixing India mark III hand pump over newly sunk for T/Well etc. all Complete | 1 | Each | 67.38 | Rs. Sixty seven and paise thirty eight only. |
| 54.12 | | Supplying all labour and material and fitting and fixing G.I Cap over the new sink T/well | 1 | Each | 65.65 | Rs. Sixty five and paise sixty five only. |
| 54.13 | | Providing all labour & tools and fitting & fixing Cylinder with requisite suspension pipe and connection rod of India mark III hand pump etc. all complete. | 1 | Each | 129.93 | Rs. One hundred twenty nine and paise ninety three only. |
| 54.14 | | Providing all labour & tools and lowering 65 mm dia G.I pipe as per specification etc. all Complete | 24 | p/m | 21.55 | Rs. Twenty one and paise fifty five only. |
| 54.15 | | Supplying labour and developing the T/Well to have sand free discharge all complete as per direction of E/I | 1 | Each | 283.31 | Rs. Two hundred eighty three and paise thirty one only. |
| 54.16 | | Providing all materials and labour and construction 1.85 dia circular P.C.C (1:2:4) UNICEF design platform with foot rest etc. all complete | 1 | Each | 3679.43 | Rs. Three thousand six hundred seventy nine and paise forty three only. |
| 54.17 | | Providing all material and labour & constructing 1 P.C.C (1:2:4) UNICEF design drain for disposal of waste water etc. all complete. | 3 | P/M | 311.08 | Rs. Three hundred eleven and paise eight only. |
| 54.18 | | Transportation of T/W materials, tools & plant from Store to work site and back to store if materials are surplus. | 1 | Each | 361.28 | Rs. Three hundred sixty one and paise twenty eight only. |
| | | Part 'C' Cost for Additional Motorised system for filling overhead water-tank | 12 | P/M | 184.36 | Rs. One hundred eighty four and paise thirty six only. |
| 54.19 | | Providing and fixing of G.I pipes complete with G.I fittings and clamps, including cutting and | | | | |
| 54.20 | | Providing and fixing brass valve 25 mm nominal bore Fullway valve , | 2 | Each | 213.06 | Rs. Two hundred thirteen and paise six only. |
| 54.21 | | 25 mm nominal bore Non-Return valve | 1 | Each | 236.90 | Rs. Two hundred thirty six and paise ninety only. |

श्री ७७७ ३०५ १७८

Chief Engineer
B.S.E.I.D.C. Ltd, Patna
21/2
28/6.
28/06/12

| | | | | | | |
|-------|---------------|---|-----|------|----------|---|
| 54.22 | | Supplying all equipments, tools and installation of 1 HP single phase submersible motor pump set of KSB/ ISI make 2900 rpm capable of discharge 5000 LPH at 45 Mtr head with all necessary riser pipe, starter control panel, 1.25" Full way valve, 1.25" M.S clamp, 1.25" G.I Elbow, 1.25" check valve, 1.25" x 9" long G.I Nipple etc. all complete as per direction of E/I | 1 | Each | 26462.00 | Rs. Twenty six thousand four hundred sixty two only. |
| 55 | | Internal Electrification Work | 153 | Each | 473.69 | Rs. Four hundred seventy three and paise sixty nine only. |
| | 1.1 | Wiring for light point/fan point/exhaust fan point/ call bell point with 1.5 sq. mm FR PVC insulated copper conductor single core cable in surface/recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size PVC/ G.I box etc. as required. | | | | |
| | 1.1.3 | Group C | | | | |
| 56 | 1.2 | Wiring for twin control light point with 1.5 sq. mm FR PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, with 2way piano type switch, phenolic laminated sheet, suitable size PVC/GI box etc. as required. | 2 | Each | 475.71 | Rs. Four hundred seventy five and paise seventy one only. |
| 57 | 1.5 | Wiring for light/ power plug with 2x4 sq. mm. FR PVC insulated, copper conductor, single core, cable in and surface, recessed PVC conduit along with 1 no. 4 sq. mm FR PVC insulated copper conductor single core cable for loop earthing as required. | 440 | mtr | 171.70 | Rs. One hundred seventy one and paise seventy only. |
| 58 | 1.7 | Wiring for circuit/ sub main wiring along with earth wire with the following size of PVC insulated, copper conductor, single core cable in surface/ recessed PVC conduit as required. | 335 | Rmt | 126.25 | Rs. One hundred twenty six and paise twenty five only. |
| | (b) 1.7.2 | 2x2.5 sq. mm + 1x2.5 sq. mm earth wire. | | | | |
| 59 | (c) 1.7.11 | 4x6 sq. mm + 1x6 sq. mm earth wire. | 25 | Rmt | 390.87 | Rs. Three hundred ninety and paise eighty seven only. |
| 60 | 1.33 | Supplying and fixing 2 pin 5 amp. Ceiling rose on the existing junction box/ PVC box including connection etc as required. | 40 | Each | 23.23 | Rs. Twenty three and paise twenty three only. |

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

24/2
28/6.

28/6/17

29/11/17

| | | | | | | |
|----|---------------|--|-----|------|---------|--|
| 61 | 1.34 | Supplying and fixing batten/ angle holder including connection as required. | 92 | Each | 28.28 | Rs. Twenty eight and paise twenty eight only. |
| 62 | 1.23 | Supplying and fixing following piano typed switch/ socket on existing switch box/ cover including connection etc. as required. | 153 | Each | 49.49 | Rs. Forty nine and paise forty nine only. |
| | 1.23.7 | Telephone socket on shutter outlet | | | | |
| 63 | 1.22 | Supplying and fixing metal box of following size (normal size) on surface or in recess with suitable size or phenolic laminated sheet cover in front of including painting etc. as required. | 6 | Each | 59.59 | Rs. Fifty nine and paise fifty nine only. |
| | 1.22.1 | 75mm X 75mm X 50mm deep (4" x 4") | | | | |
| 64 | 1.30. | Supplying and fixing suitable G.I/PVC box on surface or in recess with phenolic laminated sheet cover in front including provided and fixing 6 pin, 15/16 amps socket outlet and 15/16 amps piano type switch connection, painting etc, as required. | 46 | Each | 217.15 | Rs. Two hundred seventeen and paise fifteen only. |
| 65 | | DISTRIBUTION BOARD | 2 | Each | 2554.29 | Rs. Two thousand five hundred fifty four and paise twenty nine only. |
| | 2.9 | Supplying and fixing of following way of three pole and neutral | | | | |
| | (b) 2.9.5 | 6 way (4+18) double door | | | | |
| 66 | 2.12 | Supplying and fixing 5 amps. to 32 amps, rating, 240 volts, 'C' series, MCB of following poles in the existing MCB DB with connections, testing and commissioning etc. as required. | 35 | Each | 157.56 | Rs. One hundred fifty seven and paise fifty six only. |
| | (a) 2.12.1 | 6/32 single pole | | | | |
| 67 | (b) 2.12.5 | 6/32 TPN | 1 | Each | 936.27 | Rs. Nine hundred thirty six and paise twenty seven only. |
| 68 | 6.14 | LT Panel & Cable | 100 | mtr | 237.35 | Rs. Two hundred thirty seven and paise thirty five only. |
| | 6.14.4 | Supplying and laying following 16 sq.mm X 4 core alluminium armoured cable | | | | |
| 69 | | Trench cutting in soil of suitable size 1.5 feet wide and 2 feet depth including refilling the trench with same etc. as required. (For laying the cable) | 100 | Rmt | 22.22 | Rs. Twenty two and paise twenty two only. |

28/6/17

28/6/17
Chief Engineer
B.S.E.I.D.C. Ltd. Patna
28/6/17

| | | | | | | | |
|---|-----------|----------|--|-------------------------|-----------|---------------------|--|
| 70 | | 2.2 | Providing and fixing following capacity double pole/ TP & N sheet metal switch disconnector fuse unit in existing metal board, with ISI marked HRC fuses, including drilling holes in metal board, making connections, etc. as required. | 1 | Each | 6034.75 | Rs. Six thousand thirty four and paise seventy five only. |
| | | 2.2.2 | 100 amps. TP & N , HRC | | | | |
| 71 | | | EARTHING | 3 | Each | 123.22 | Rs. One hundred twenty three and paise twenty two only. |
| | | 3.15 | Providing and laying earth conection from earth electrod with 6 SWG dia GI wire in 15 mm dia GI pipe from earth electrod , as required. | | | | |
| 72 | | 3.6 | E arthing with copper earth plate 600mmx600mmx3mm thick including accesssoies, and providing masonary enclosure with cover plate having locking arrangement and watering pipe etc as required | 1 | Set | 5633.78 | Rs. Five thousand six hundred thirty three and paise seventy eight only. |
| 73 | | | MISCELLANEOUS WORK | 177.47 | CU.M | 164.4 | Rs. One hundred sixty four and paise forty only. |
| | | | CARRAIGE OF MATERIALS | | | | |
| | 73.1 | | A) LOCAL SAND ,Avg. LEAD - 3 KM. | | | | |
| | 73.2 | 60 Km | B) COARSE SAND ,Avg. LEAD from Jagdishpur | 214.48 | CU.M | 804.00 | Rs. Eight hundred four only. |
| | 73.3 | 64 Km | C) STONE CHIPS ,Avg. LEAD from Tinpahar | 194.85 | CU.M | 869.14 | Rs. Eight hundred sixty nine and paise fourteen only. |
| | 73.4 | | D) BRICKS ,Avg. LEAD- = 8 KM. | 93.33 | THOUSA ND | 557.36 | Rs. Five hundred fifty seven and paise thirty six only. |
| | 73.5 | | E) Cement ,Avg. Lead =5 KM. | 2409.00 | Bags | 9.88 | Rs. Nine and paise eighty eight only.. |
| | 73.6 | | F) Steel ,Avg. Lead =5 KM. | 14.85 | M.T. | 197.50 | Rs. One hundred ninety seven and paise fifty only. |
| 74 | | | Add extra cost of material for Bhagalpur Commissionary w.r.t Gaya as per SOR, BCD | 93.33 | THOUSA ND | 269.85 | Rs. Two hundred sixty nine and paise eighty five only. |
| | 74.1 | | Bricks | | | | |
| | 74.2 | | Cement | 2409.00 | Bags | 41.54 | Rs. Forty one and paise fifty four only. |
| | | | | TOTAL Cost = Rs. | | 5,239,859.25 | |
| Group No. : USS-127B | | | | | | | |
| S.N. | District | Block | Name of School | | | | |
| 1 | BHAGALPUR | Pirpaiti | M.S. Maulola | | | | |
| | | | | | | Rs | 5,239,859.25 |
| | | | | | | Say | 5,239,859.00 |
| Tender approved in favour of Manoj kumar singh. @ 6.00% (Six Decimal Zero Percent) below BOQ rates i.e.total amount comes to Rs. 49,25,467=00 (Rupees Forty Nine Lacs Twenty Five Thousand Four Hundred Sixty Seven Only) | | | | | | | |

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

24/6
28/628/6/12
28/06/12

Performance Security

Name of Agency – “Manoj Kumar Singh”

Performance Security of “Manoj Kumar Singh” of “USS-127B”

FDR No.

36754757557

DOI

13.04.17 To 13.04.18

Amount

247000.00

(Rupees Two Lacs Forty Seven Thousands Only)

Amir K. San

लेखा पदाधिकारी

15/6/17

बिहार राज्य शैक्षणिक आधारभूत संरचना
विकास निगम लि० पटना

[Signature]

15/6/17

मनोज कुमार सिंह

Chief Engineer

B.S.E.I.D.C. Ltd, Patna

[Signature]
28/6.

BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. Of Bihar Undertaking)

Shiksha Bhawan, Bihar Rastrabhasa Parishad Campus, Acharya Shiv Pujan Sahay Path, Saidpur,
PATNA-800004. (Tel. No: 0612-2910314)

Letter of Acceptance

Letter no :- BSEIDC/TECH/164/2013-

Patna, Date... 25.5.2014

With reference to N.I.T. No.-44/2013-14, Dated-30.12.2013 for execution of "Construction of Upgraded Secondary School buildings in Bihar" the bids have been accepted in favour of the Agencies as per details below:-

| | Name of Groups | Name of District | Name of Block | Name of School | Name of Agency | Estimated Cost (in Rs.) | Tendered Valur (in Rs.) | Performance security to be deposited (in Rs.) | Tim Con ion |
|----|----------------|------------------|---------------|------------------------------|---|-------------------------|-------------------------|---|-------------|
| 1 | USS-102 (A) | Nalanda | Biharsarif | M.S. Mahanandpur | Girdhar Gopal Murari Sinha, Vill+P.O.- Doiyya, Via- Sohasarai, Nalanda. | 53,30,289.00 | 48,76,681.00 | 244000 | 12 |
| 2 | USS-102 (B) | | Biharsarif | M.S.Majidpur | Arbind Prasad, Purankama, Sheikhpura, Pin-811105. | 53,30,289.00 | 50,57,911.00 | 253000 | 12 |
| 3 | USS-102 (C) | | Chandi | M.S.Dariya Bigha | Roy Engineers, Basant Vihar Colony, Raghunath Path, Near Plastic Factory, R.P.S. Road, Danapur, Patna-801503. | 53,67,934.00 | 50,32,438.00 | 252000 | 12 |
| 4 | USS-102 (E) | | Noorsarai | M.S.Michaiganj sakroua | Prakash Construction, Vill+P.O.- Nahub, P.S.- Rajgir, Distt.- Nalanda. | 53,49,218.00 | 52,17,627.00 | 261000 | 12 |
| 5 | USS-110 (A) | Bhojpur | Barhara | U.M.S.Saligram singh ka Tola | Rakesh Tiwari, AT+P.O.- Ramsahar, Barhara, Distt.- Bhojpur. | 52,07,256.00 | 48,65,660.00 | 244000 | 12 |
| 6 | USS-110 (D) | | Koilwar | M.S. Khesarhiyan | Ritu Singh, Vill- Semeia, Barhara, Distt.-Bhojpur. | 51,90,908.00 | 48,40,003.00 | 243000 | 12 |
| 7 | USS-110 (E) | | Koilwar | M.S. Khangaown | Avanish Kumar, Vill+P.O.- Amhara, Bihta, Patna. | 51,96,931.00 | 46,77,238.00 | 234000 | 12 |
| 8 | USS-116 (B) | | Dumraon | M.S. Kanjharua | Shailendra Choubey, Vill+P.O.- Purana, Bhojpur, Distt.- Buxar, Bihar. | 53,45,916.00 | 52,89,543.00 | 265000 | 12 |
| 9 | USS-116 (D) | | Dumraon | M.S.Karuaj | Shailendra Choubey, Vill+P.O.- Purana, Bhojpur, Distt.- Buxar, Bihar. | 53,51,928.00 | 52,33,650.00 | 262000 | 12 |
| 10 | USS-117 (A) | Buxar | Nawanagar | M.S. Pramanpur | M/S Surbendra Kumar & Co., Civil Line, Buxar. | 53,98,754.00 | 51,12,620.00 | 256000 | 12 |
| 11 | USS-121 (E) | | Akorhigol | M.S. chhapra | Kamal Technocrate Pvt. Ltd., New Dilian, Dehri on sone, Rohtas. | 51,86,503.00 | 47,95,440.00 | 240000 | 12 |
| 12 | USS-127 (B) | | Pirpaiti | M.S. Moultoia | Manoj Kumar Singh, Vasantpur, Pipainti, Bhagalpur. | 52,39,859.00 | 49,25,467.00 | 247000 | 12 |
| 13 | USS-144 (A) | Jehanabad | Hulasganj | M.S.vira | Kaushlendra Kumar, Bazar Samiti, Raja Bazar, Jehanabad. | 50,17,738.00 | 49,72,076.00 | 249000 | 12 |
| 14 | USS-144 (B) | | Makhdumpur | M.S.Akbarpur | Bhupesh Kumar, Vill+P.O - Chiraura, P.S.- Naubatpur, Patna | 50,13,435.00 | 47,24,159.00 | 237000 | 12 |
| 15 | USS-146 (C) | | Paharibaran | M.S. Deodha | Keeran Devi, Vill- Gotrain, P.O.+P.S.- Nardiganj, Distt.- Nawada | 52,13,535.00 | 52,88,000.00 | 260000 | 12 |

Chief Engineer


BSEIDC Ltd Patna

28/6

Agencies are hereby requested to furnish performance security as per mentioned in above table. The Performance Security should be deposited within 10 (Ten) days of receipt of this Letter of Acceptance (LOA) valid up to 28 (Twenty eight) days from the date of expiry of defect liability period.

In the interest of the work Agencies are instructed to proceed with the execution of the said work in consultation with concerned Engineer-in-Charge with immediate effect. The date of start of this work will be the date of issue of this letter. The agreement will be executed after verification of Performance Security and Registration in appropriate category in this Corporation.


Yours faithfully



(Brajesh Prasad)
Chief Engineer

Memo no: BSEIDC/TECH/164/2013-

Patna, Date.....

Copy forwarded to : i) Executive Engineer I/C of the Project.
ii) Senior Account Officer, BSEIDC, Patna.


(Brajesh Prasad)
Chief Engineer


Chief Engineer
B.S.E.I.D.C. Ltd, Patna

24/6
28/6

गंगा डमरु

SPECIAL CONDITIONS

1. The tenderers are required to deposit the earnest money as prescribed in the NIT.
2. Every page should be signed by the Tenderer. In the event of tender being submitted by a firm, the tender should be signed by the person holding proper power of attorney and the copy of the same should also be submitted.
3. The rates quoted by the contractor should be inclusive of all taxes royalties and other incidental charges.
4. To qualify for award of work, the Bidder must possess the following :-
 - a) Legal Status, Place of Registration, Principal place of business & Power of attorney of signatory bid.
 - b) DD for required value of B.O.Q. Cost.
 - c) Sufficient Earnest Money Deposit.
 - d) Certificate from Chartered Accountant of Annual Financial Turn over usually not less than 50 % of the estimated cost of works for which bid has been invited in any one year and to be submitted for last five years as mentioned in Technical bid.
 - e) Certificate from EE / Concerned Authority for Work Experience of Similar nature (Satisfactory completed atleast one Building work of value not less than 25 % of estimated value of contract) in last five years and current Financial year will also be considered as mentioned in Technical bid.
 - f) Litigation History as mentioned in Technical bid.
 - g) Affidavit as mentioned in Technical bid.
 - h) Valid Registration with Central/ State Govt. / PSU.
 - i) Valid labour license as mentioned in Technical bid.
 - j) Valid Character Certificate as mentioned in Technical bid.
 - k) Affidavit/Certificate for not been debarred as mentioned in Technical bid.
5. Contractor should satisfy themselves fully about the nature, site of work before offering their tender and place of any ignorance afterwards shall not be considered.
6. The tender without earnest money or insufficient earnest money submitted with the tender, will be outright rejected.
7. Conditional tenders shall be outright rejected.
8. After approval of rates by the competent authority the contractor shall have to deposit the initial security money within 10 days of the receipt of the written work order failing which his tender shall be rejected and earnest money forfeited.
9. Authority shall reserve the right to reject any or all the tenders or distribute the work to more than one contractor without assigning any reason.
10. Any claim for idle labours on any account shall not be entertained.
11. The contractor shall arrange necessary site for accommodation and other facilities like medical etc. For his labour on his own cost and initially will comply with labour rules prevalent in the locality.
12. The contractor shall be solely responsible for any damage occurred at site due to negligence of the labour or other staff and any damage shall be recovered from the contractor.
13. It will be obligatory on the part of the tenderer to keep his tender open for 120 days from the date of opening of tender.
14. The contractor shall not be entitled to any claim or compensation on account of any loss suffered by him due to :-

a. Natural calamities

(Seal & Signature of Tenderer)

Page 1 of 2

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

242
28/6

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लिमिटेड

(बिहार सरकार का एक उपक्रम)

शिक्षा भवन, बिहार राष्ट्रभाषा परिषद् कैम्पस, आचार्य शिवपुजन सहाय पथ, सैदपुर, पटना-800004 (दूरभाष:-0612-2910314)

पुनर्निविदा आमंत्रण सूचना संख्या-44 वर्ष 2013-14

प्रतिशत मद दर निविदा

(केवल ई-टेंडरिंग पद्धति के अनुसार वेबसाइट www.eproc.bihar.gov.in पर)

1. शिक्षा विभाग, बिहार के अन्तर्गत उत्क्रमित माध्यमिक विद्यालयों के भवन निर्माण कार्य हेतु निम्नांकित निविदायें पनः आमंत्रित की जाती हैं। कोई भी संवेदक जो केन्द्रीय/राज्य सरकार/सार्वजनिक क्षेत्रों में निबंधित हो, निविदा में भाग ले सकते हैं परन्तु इस निगम का रजिस्ट्रेशन कराना, उक्त कार्य का लेटर ऑफ एक्सेप्टेंस प्राप्त होने के बाद अनिवार्य होगा।

| क्र म | युप संख्या | जिला का नाम | प्रखण्ड का नाम | विद्यालय का नाम | प्राक्कलित राशि (लाख रु०) | अग्रघन की राशि (लाख रु०) | परिमाण विपत्र की राशि(रु०) | कार्य समाप्ति की अवधि |
|-------|-------------|-------------|----------------|-----------------|------------------------------------|--------------------------|----------------------------|-----------------------|
| 1 | USS-102 (A) | Nalanda | 1 | Biharsarif | M.S. Mahanandpur | 53.31 | 1.070 | 11,150 |
| 2 | USS-102 (B) | | 2 | Biharsarif | M.S.Majidpur | 53.31 | 1.070 | 11,150 |
| 3 | USS-102 (C) | | 3 | Chandi | M.S.Dariya Bigha | 53.68 | 1.075 | 11,150 |
| 4 | USS-102 (D) | | 4 | Chandi | Urdu.M.S.Baisa | 53.68 | 1.075 | 11,150 |
| 5 | USS-102 (E) | | 5 | Noorsarai | M.S.Michaiganj sakroua | 53.50 | 1.070 | 11,150 |
| 6 | USS-102 (F) | | 6 | Sarmara | M.S. Singhaul | 53.88 | 1.080 | 11,150 |
| 7 | USS-110 (A) | Bhojpur | 1 | Barhara | U.M.S.Saligram singh ka Tola | 52.08 | 1.045 | 11,150 |
| 8 | USS-110 (B) | | 2 | Barhara | M.S. Pakri | 51.98 | 1.040 | 11,150 |
| 9 | USS-110 (C) | | 3 | Barhara | Govt. M.S.Bakhorapur | 51.97 | 1.040 | 11,150 |
| 10 | USS-110 (D) | | 4 | Koilwar | M.S. Khesarhiyan | 51.91 | 1.040 | 11,150 |
| 11 | USS-110 (E) | | 5 | Koilwar | M.S. Khangaown | 51.97 | 1.040 | 11,150 |
| 12 | USS-116 (A) | Buxar | 1 | Dumraon | M.S. Nuaon | 53.45 | 1.070 | 11,150 |
| 13 | USS-116 (B) | | 2 | Dumraon | M.S. Kanjharua | 53.49 | 1.070 | 11,150 |
| 14 | USS-116 (C) | | 3 | Dumraon | M.S. Mathila | 53.52 | 1.075 | 11,150 |
| 15 | USS-116 (D) | | 4 | Dumraon | M.S.Karuaaj | 53.52 | 1.075 | 11,150 |
| 16 | USS-116 (E) | | 5 | Dumraon | M.S. Rampur Mathiya | 53.52 | 1.075 | 11,150 |
| 17 | USS-117 (A) | Buxar | 1 | Nawanagar | M.S. Pramanpur | 53.99 | 1.080 | 11,150 |
| 18 | USS-117 (B) | | 2 | Ithari | M.S. Barkagaon | 53.37 | 1.070 | 11,150 |
| 19 | USS-117 (C) | | 3 | Ithari | M.S. Harpur | 53.20 | 1.065 | 11,150 |
| 20 | USS-117 (D) | | 4 | Ithari | M.S.Basawan Kala | 53.20 | 1.065 | 11,150 |
| 21 | USS-119 (A) | Kaimur | 1 | Bhabhua | M.S. Miun | 53.65 | 1.075 | 11,150 |
| 22 | USS-119 (B) | | 2 | Bhabhua | M.S. Piliyan | 53.65 | 1.075 | 11,150 |
| 23 | USS-119 (C) | | 3 | Bhabhua | M.S. Mehluan | 53.65 | 1.075 | 11,150 |
| 24 | USS-119 (D) | | 4 | Bhabhua | M.S. Mohan Darwan | 53.65 | 1.075 | 11,150 |
| 25 | USS-120 (A) | Kaimur | 1 | Ramgarh | M.S. Sijhua | 53.71 | 1.075 | 11,150 |
| 26 | USS-120 (B) | | 2 | Ramgarh | M.S. Upari | 53.71 | 1.080 | 11,150 |
| 27 | USS-120 (C) | | 3 | Nuaon | Govt. Basic School Kari Ram Akhili | 53.86 | 1.080 | 11,150 |
| 28 | USS-120 (D) | | 4 | Nuaon | M.S. Mushiyen | 53.86 | 1.080 | 11,150 |
| 29 | USS-120 (E) | | 5 | Durgawati | U.M.S. Nuaon | 53.86 | 1.080 | 11,150 |
| 30 | USS-121 (A) | Rohtas | 1 | Karakat | M.S. Devmarkande | 52.39 | 1.050 | 11,150 |
| 31 | USS-121 (B) | | 2 | Karakat | Girl M.S. Motha | 52.51 | 1.055 | 11,150 |
| 32 | USS-121 (C) | | 3 | Nasriganj | M.S. Paiga | 52.08 | 1.045 | 11,150 |
| 33 | USS-121 (D) | | 4 | Nasriganj | M.S.Pawani | 52.20 | 1.045 | 11,150 |
| 34 | USS-121 (E) | | 5 | Akorhigola | M.S. chhapra | 51.87 | 1.040 | 11,150 |
| 35 | USS-126 (A) | Bhagalpur | 1 | Kahalgaon | M.S. Basudeopur Bhuluya | 52.23 | 1.045 | 11,150 |
| 36 | USS-126 (B) | | 2 | Kahalgaon | M.S. Maheshmunda | 52.23 | 1.045 | 11,150 |
| 37 | USS-126 (C) | | 3 | Kahalgaon | M.S.Ekdara | 52.07 | 1.045 | 11,150 |
| 38 | USS-126 (D) | | 4 | Kahalgaon | M.S.Saur | 52.23 | 1.045 | 11,150 |

मोहन जमाल

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

248.
28/6.

| | | | | | | | | | |
|-----|-------------|----------------|---|--------------|------------------------------------|-------|-------|--------|--------|
| 102 | USS-173 (A) | Siwan | 1 | Husainganj | M.S. Hata Tola Chhata | 56.41 | 1.130 | 11,150 | 12 माह |
| | USS-173 (B) | | 2 | Raghunathpur | M.S. Kandhauri | 56.80 | 1.140 | 11,150 | |
| 103 | USS-192 (A) | Darbhanga | 1 | Bahadurpur | M.S. Daing | 56.72 | 1.135 | 11,150 | 12 माह |
| 104 | USS-192 (B) | | 2 | Biraul | M.S. Koilajan | 57.70 | 1.155 | 11,150 | |
| 105 | USS-192 (C) | | 3 | Benipur | U. M.S. Ramouli | 57.33 | 1.150 | 11,150 | |
| 106 | USS-192 (D) | | 4 | Biraul | U.M.S. Balha | 57.70 | 1.155 | 11,150 | |
| 107 | USS-196 (A) | Katihar | 1 | Pranpur | Middle School Kast Hawar | 56.17 | 1.125 | 11,150 | 12 माह |
| 108 | USS-196 (B) | | 2 | Ajamnagar | Middle School Arihana | 56.44 | 1.130 | 11,150 | |
| 109 | USS-196 (C) | | 3 | Ajamnagar | Middle School Dhena Bagchhala | 56.88 | 1.140 | 11,150 | |
| 110 | USS-196 (D) | | 4 | Pranpur | Middle School Ghanhar Vighocha | 56.17 | 1.125 | 11,150 | |
| 111 | USS-197 (A) | Katihar | 1 | Barsoi | Middle School Barsoi Ghat | 56.96 | 1.140 | 11,150 | 12 माह |
| 112 | USS-197 (B) | | 2 | Dhankhora | Middle School Durgasthan Dhankhora | 56.11 | 1.125 | 11,150 | |
| 113 | USS-197 (C) | | 3 | Kodha | Middle School Marwa Najrachowki | 56.10 | 1.125 | 11,150 | |
| 114 | USS-197 (D) | | 4 | Kadwa | Dukhi Ram Middle School Chandpur | 56.10 | 1.125 | 11,150 | |
| 115 | USS-199 (A) | Araria | 1 | Forbisganj | Adarsh Middle School Mirjapur | 56.91 | 1.140 | 11,150 | 12 माह |
| 116 | USS-199 (B) | | 2 | Forbisganj | Middle School Hingna Aurahi | 57.31 | 1.150 | 11,150 | |
| 117 | USS-199 (C) | | 3 | Narpatganj | Middle School Khabdah Dumriya | 57.70 | 1.155 | 11,150 | |
| 118 | USS-199 (D) | | 4 | Narpatganj | Middle School Achra | 57.70 | 1.155 | 11,150 | |
| 119 | USS-199 (C) | Saharsa | 1 | Banma Ithari | Middle School Ithari | 57.80 | 1.160 | 11,150 | 12 माह |
| 120 | USS-209 | West Champaran | 1 | Bagha-II | Middle School, Ratanpurva | 56.89 | 1.138 | 11,150 | 12 माह |
| 121 | USS-211 | Gopalganj | 1 | Uchkagaon | Middle School, Kaparpura | 55.98 | 1.120 | 11,150 | 12 माह |
| 122 | USS-217 | Madhubani | 1 | Khutauna | Middle School, Ekhattha | 58.42 | 1.17 | 11,150 | 12 माह |

नोट:-1. निविदाकार एक या अधिक ग्रुप में अलग-अलग निविदा डाल सकते हैं।

2. प्राकल्पित राशि घट या बढ़ सकती है एवं तदनुसार अग्रधन की राशि घट या बढ़ सकती है।

- (2) विज्ञापन निर्गत करने की तिथि :- दिनांक:- 13.02.2014
- (3) परिमाण विपत्र प्राप्त करने(डाउनलोड) की अवधि एवं समय :- दिनांक- 22.02.2014 से 17.03.2014, 15:00 घंटा
(वेबसाइट: www.eproc.bihar.gov.in पर)
- (4) प्री बिड मीटिंग का समय, स्थान एवं तिथि :- दिनांक:- 28.02.2014, 14:30 घंटा प्रबंध निदेशक का कार्यालय, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम, पटना।
- (5) निविदा प्राप्ति(अपलोड) की अंतिम तिथि एवं समय :- दिनांक:- 18.03.2014, समय- 15:00 घंटा
- (6) टेक्निकल बिड खोलने की तिथि एवं समय :- दिनांक:- 24.03.2014, समय- 15:30 घंटा
(वेबसाइट-www.eproc.bihar.gov.in पर)
- (7) वित्तीय बिड खोलने की तिथि एवं समय :- दिनांक:- 02.04.2014, समय- 16:00 घंटा
- (8) निविदा खोलने का स्थान :- वेबसाइट-www.eproc.bihar.gov.in पर
- (9) निविदा की वैधता की अवधि :- 120 दिन

(10) ई-टेन्डरिंग की प्रक्रिया में भाग लेने हेतु संवेदकों को पंजीकृत होना होगा, जिससे कि उन्हें उपयोगकर्ता का नाम (user ID) पासवर्ड (Password) अंकीय हस्ताक्षर (Digital Signature) निर्गत की जायेगी। यह उन्हें वेबसाइट www.eproc.bihar.gov.in से डाउनलोड करने/टेन्डर की प्रक्रिया में भाग लेने की योग्यता प्रदान करेगा।

(11) ई-निविदा पत्र वेबसाइट www.eproc.bihar.gov.in से प्राप्त किया जा सकता है। संवेदक द्वारा सिर्फ उपर्युक्त वेबसाइट से ही परिमाण विपत्र प्राप्त करने के उपरान्त वेबसाइट पर ही इलेक्ट्रॉनिक निविदा पत्र को भरकर भेजना है। अन्य सभी महत्वपूर्ण कागजात/बैंक ड्राफ्ट/अग्रधन की राशि/सभी प्रमाण पत्र जो निविदा के लिए आवश्यक है को स्कैन कर ई-निविदा के साथ संलग्न करना अनिवार्य है।

(12) परिमाण विपत्र के दर से कम दर उद्धृत करने पर बीड डाक्यूमेंट की शर्तों एवं सरकारी निर्णयानुसार अतिरिक्त Performance Guarantee एंकरनामा के पूर्व जमा करना होगा।

(13) (क) प्रत्येक परिमाण विपत्र का मूल्य जो प्रत्येक निविदा के सामने उपर कण्डिका (1) में अंकित है (जो लौटाया नहीं जाएगा) किसी भी राष्ट्रीयकृत बैंक द्वारा निर्गत एवं BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD. के नाम से एवं पटना में भुगतान हो, स्वीकार किया जायेगा। मूल बैंक ड्राफ्ट "बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम, पटना" के नाम से एवं पटना में भुगतान हो, स्वीकार किया जायेगा।

मन्त्र. उमम. निरु

244.
28/6